



CITY OF PERRIS

PLANNING COMMISSION AGENDA SUBMITTAL

MEETING DATE: May 17, 2023

SUBJECT: Specific Plan Amendment (SPA) 21-05267, Tentative Parcel Map 21-05086 (TPM-38259), Development Plan Review (DPR) 21-00005 – A proposal to consider the following entitlements to facilitate the construction of a 764,753 square-foot industrial warehouse facility: 1) Specific Plan Amendment to vacate unimproved California Avenue and Nance Street from the Circulation Plan in the Perris Valley Commerce Center Specific Plan (PVCCSP); 2) Tentative Parcel Map to consolidate 38 existing parcels into one (1) 35.63 acre-parcel; 3) Development Plan Review for the site plan and building elevations. The 35.63-acre project site is located south of Harley Knox Boulevard between Patterson Avenue and Nevada Avenue, in the GI - General Industrial and LI - Light Industrial Zones. (APNs: 314-153-015 through -040, 314-153-042, 314-153-044, -046, -048, 314-160,005 through -012, and 314-160-033. Applicant: Nicole Torsvet, Patterson Limited Partnership.

REQUEST: Adopt Resolution 23-11 recommending that the City Council certify the Final Environmental Impact Report (SCH 2022010274), adopt the Mitigation and Monitoring and Reporting Program, and approve Specific Plan Amendment 21-05267, Tentative Parcel Map 21-05086 (TPM-38259), Development Plan Review 21-00005 to facilitate the construction of a 764,753 square foot industrial distribution building, based on the findings and the Conditions of Approval.

CONTACT: Kenneth Phung, Director of Development Services Department

BACKGROUND

The project site comprises 38 parcels, totaling 35.63 acres. The terrain consists of exposed soil with moderate to dense non-native grass and weeds. Approximately 26.31 acres of the site are zoned GI - General Industrial, and the remaining 9.32 acres are zoned LI - Light Industrial. The northwest corner of the site has historically been used for the storage of trucks and trailers. During a site visit, staff noted that six trailers were stored on site. Surrounding uses include commercial uses to the north; vacant land and two legal, non-conforming residences to the east; industrial uses and a non-conforming residence to the west; and an industrial warehouse to the south.

As a matter of information, on April 20, 2021, the Planning Commission conducted a public Scoping meeting to review and discuss the preparation of an Environmental Impact Report (EIR) for the development of the site with a 764,753 square-foot industrial warehouse facility. Some of the topics discussed by the Planning Commissioners include requesting a detailed traffic analysis, solar panels installation (i.e., will require ALUC approval), electronic vehicle (EV) charging stations (i.e., developer will provide EV charging stations), and circulation (i.e., the site circulation will separate truck and auto access). Also, a representative of Care California inquired about issues such as greenhouse gas emissions (GHG), noise, and hazardous materials. Three Center for Community Action and Environmental Justice (CCA EJ) members expressed concerns regarding GHG, circulation, the need for EV stations, and designated truck routes. Comments expressed at the Scoping Meeting have been addressed in the Project specific EIR.

PROJECT DESCRIPTION

The applicant is requesting approval of the following development applications to facilitate the development of the subject site with a 754,359-square-foot non-refrigerated warehouse distribution facility: 1) Specific Plan Amendment to vacate unimproved California Avenue and Nance Street from the Circulation Plan of the Perris Valley Commerce Center Specific Plan (PVCCSP); 2) Tentative Parcel Map (TPM-38292) to consolidate 38 existing parcels into one (1) 35.63 acre-parcel; and 3) Development Plan Review for the site design and building elevations of the proposed project.

The proposed warehouse distribution facility consists of a 754,359 square feet warehouse area and 10,394 square feet of office space, which includes a 5,269-square foot ground floor office, and a 5,125-square foot mezzanine office. A total of 113 loading dock doors are proposed, with 49 dock doors on the west side of the building and 64 dock doors on the east side. A 14-foot-high decorative masonry screen wall is proposed around the perimeter of the loading area. The project will be served by 333 parking spaces located on the north and southwest area of the site. A total of 17 parking spaces will be Electric Vehicle (EV) spaces, and 124 will be EV-ready spaces. The project also provides 137 trailer parking spaces on the project site.

Access to passenger vehicles is provided via two 30-foot wide driveways on Patterson Avenue. In addition, there are two additional 50 and 58-foot wide driveways on Patterson Avenue that will provide separate truck access and circulation around the cross-dock building. Access for emergency vehicles is provided via a driveway off Nevada Avenue. There is no co-mingling of passenger vehicles and trucks on-site. Trucks are anticipated to access the I-215 Freeway by exiting the project site via Patterson Avenue to Harley Knox Boulevard, consistent with the City's adopted truck route.

PROJECT ANALYSIS

The following table summarizes the project's consistency with the General Plan, Perris Valley Commerce Center Specific Plan, Title 19 - Zoning Code, Title 18 - Subdivision Code, and March Air Reserve Base/Inland Port Airport Land Use Compatibility Plan.

	Consistent	Inconsistent
<p>Consistency with the General Plan</p> <p>The project is in Planning Area 1 (North Commercial/Industrial) of the General Plan, which allows industrial and commercial opportunities due to the area's proximity to the I-215 freeway and the proximity to March Global Port. As proposed, the project will be consistent with the General Plan and will further the following General Plan Circulation Element goals:</p> <ul style="list-style-type: none"> ○ Goal II – A well-planned, designed, constructed, and maintained street and highway system that facilitates the movement of vehicles and provides safe and convenient access to surrounding developments. ○ Goal V - Efficient goods movement. <ul style="list-style-type: none"> - V.A.8: Require streets abutting properties in General Industrial (GI) and Light Industrial (LI) Zones to conform to standard specifications for industrial collector streets to accommodate the movement of heavy trucks. - V.A.8: Provide adequate off-street loading areas for all manufacturing land uses. 	<input checked="" type="checkbox"/>	<input type="checkbox"/>
<p>Consistency with the Perris Valley Commerce Center Specific Plan (PVCCSP) and Title 19 - Zoning Code</p> <p>The project site is in the GI – General Industrial and LI – Light Industrial Zones of the PVCCSP, which are intended for industrial warehouse distribution buildings. The proposed industrial warehouse facility is permitted in the GI and LI Zones and is consistent with the development standards of the underlying zones. Therefore, the project is consistent with the PVCCSP and Zoning Code (Exhibit C).</p>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
<p>Consistency with Title 18 – Subdivisions Code</p> <p>The Tentative Parcel Map will consolidate 38 parcels into one (1) 35.63 acre parcel and vacate unimproved California Avenue and Nance Street to facilitate the construction of the proposed 764,753-square-foot warehouse building. The consolidated parcel and vacation of the paper/unimproved streets comply with Title 18 – Subdivisions Code (Exhibit F).</p>	<input checked="" type="checkbox"/>	<input type="checkbox"/>

	Consistent	Inconsistent
<p>Consistency with the March Air Reserve Base/Inland Port Airport Land Use Compatibility Plan (MARB/IPA ALUCP)</p> <p>The Project site is located within Zone B2 (Primary Approach/Departure Zone) of the MARB/IPA ALUCP. The B2 Zone is considered to have a moderate to high noise impact (Exhibit D) and does not permit any residential development, and any commercial development. It is limited to no more than 100 people per acre based upon the building's square footage. Additionally, On August 23, 2022, the ALUC considered this project and determined to be conditionally consistent with the MARB/IPA ALUCP.</p>	<input checked="" type="checkbox"/>	<input type="checkbox"/>

COMPLIANCE WITH APPLICABLE DEVELOPMENT STANDARDS

The tables below summarize compliance with the PVCCSP Development Standards for the General Industrial (GI) and Light Industrial (LI) Zones and Chapter 19.69 – Zoning Code Parking Development Standards.

Perris Valley Commerce Center Specific Plan General and Light Industrial Zones - Development Standards					
	Standard		Proposed	Consistent	Inconsistent
Lot Coverage	50 percent maximum		48 percent	<input checked="" type="checkbox"/>	<input type="checkbox"/>
FAR (Floor Area Ratio)	0.75		0.49	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Minimum Lot Size	15,000 square feet (0.34 acres)		35.63 acres	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Minimum Lot Width	75 feet		779 feet	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Minimum Lot Depth	100 feet		1,284 feet	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Building Height	50 feet		47 feet	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Setbacks	Front Yard: West – Patterson Ave	10 feet	181 feet	<input checked="" type="checkbox"/>	<input type="checkbox"/>
	Rear Yard: East – Nevada Ave.	None	252.5 feet		
	Interior Side Yards: North South	None	165 feet 61.5 feet	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Landscape Coverage	10 percent – GI Zone		12 percent		
	12 percent – LI Zone		12 percent	<input checked="" type="checkbox"/>	<input type="checkbox"/>

Zoning Code – Chapter 19-69 - Parking and Loading Standards					
Parking Standards					
Use	Standard	Required	Proposed	Consistent	Inconsistent
Industrial Building	Warehouse: 764,753 s.f. 20,000 s.f. (1space/1000 s.f.)	20 spaces	333 spaces	<input checked="" type="checkbox"/>	<input type="checkbox"/>
	20,000 – 40,000 s.f. (1 space /2000 s.f.)	10 spaces			
	Over 40,000 s.f. (1 space/5000 s.f.)	145 spaces			
Total Parking		175 spaces	333 spaces	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Total Surplus Parking			158 spaces	<input checked="" type="checkbox"/>	<input type="checkbox"/>

COMPLIANCE WITH OTHER APPLICABLE REQUIREMENTS

- Building Elevations**

The proposed building elevations reflect a contemporary industry-standard architectural style for concrete tilt-up industrial buildings. The design combines varying rooflines, cornice treatment, vertical and horizontal windows, and the façade treatment of textured formliners to create a contrasting design. The proposed design complies with the Perris Valley Commerce Center Specific Plan design standards. The entry areas include textured formliners in dark grey (Ellie Gray), which helps to provide a sense of depth on an expansive linear and utilitarian building plane. The proposed color palette combines two different shades of gray (Ice Cube and Lazy Gray), white (Pure White), and a darker trim (Iron Ore) as an accent color to create contrast and complement the entire building. The combination of various colors, recessed entryways for the office, variable roof height, cornice treatments, and windows provides visual interest to the building. Rooftop equipment will be screened and not visible from adjacent streets (Exhibit G).

- Employee Amenity and Recreation area**

Buildings over 100,000 square feet must have at least one (1) indoor employee amenity and two (2) outdoor employee amenities. The proposed project includes two outdoor amenity areas: a landscaped concrete lunch patio and a seating area covered with a trellis structure located on the northwest and southwest sides of the site for employee convenience and privacy. An indoor amenity area that can be used for either basketball, ping pong, or other related indoor activity is proposed on the northwest area of the building. As proposed, the project amenities comply with the requirements of the Code (Exhibit G).

- Landscaping**

The proposed conceptual landscape plan conforms to the Landscaping Ordinance's requirements. The project consists of 185,221 square feet or 12 percent of landscape

coverage. The minimum coverage for the General Industrial Zone is 10 percent, and 12 percent for the Light Industrial Zone.

The site has a rich palette of ground cover, shrubs, trees, and accent trees at the entry points throughout the project site. Plans show a harmonious blend of plant materials along the entire street frontage of Patterson and Nevada Avenues. In order to screen the access drive aisle along Patterson Avenue, staff is recommending relocating the 14-foot-high screen wall 20 feet from the property line and berming the landscape planter in front of it to soften the screen wall from the street. As part of this project, a 40-foot wide landscape planter with a 2:1 slope is proposed along the Nevada Avenue frontage in front of the 14-foot-high screen wall to also soften the view of the wall. (Exhibit G).

Plans show limited landscaping along the north side of the site. The Zoning Code requires a tree for every six (6) parking spaces. Therefore, staff recommends a condition of approval requiring evergreen trees be planted throughout the parking lot on the northerly side for compliance with the Code.

- **Fencing/Walls**

Two 14-foot-high walls with pilasters are proposed along the east and west sides of the Project site to screen views of the loading docks and truck parking areas along the Patterson and Nevada Avenues frontages. The drive aisle extending parallel to Patterson Avenue for truck access to the loading area is readily visible from the street. As such, staff is recommending a condition of approval requiring the screen wall to be relocated 20 feet from the front property line parallel to Patterson Avenue. The applicant has agreed to the condition of approval. With the relocation of the screen wall, the truck drive aisle and loading docks, and truck parking area will be screened from Patterson Avenue and in conformance with the design standards of the PVCCSP. Additionally, staff is also recommending a condition of approval requiring the gates to have a perforated metal mesh to help obscure visibility into the loading areas.

A 3-foot-high retaining wall with an 8-foot-high tubular steel fence is proposed along the north property line for separation purposes and will be constructed adjacent to the existing chain link fence and block wall. Staff is also recommending a condition of approval to extend the proposed 8-foot-high tubular steel fence on the north property line to 10 feet from the front property line along Patterson Avenue.

ENVIRONMENTAL CONSIDERATIONS AND CEQA PROCESS

An Environmental Impact Report (SCH 2022010274) has been completed in compliance with the California Environmental Quality Act (CEQA) Guidelines (Exhibit (H)). The EIR concludes that all impacts related to aesthetics, air quality, biological resources, cultural resources, energy, geology and soil, greenhouse gas emissions, hazards, noise, transportation, and tribal cultural resources have been reduced to less than significant or have been reduced to below the level of significance with the implementation of mitigation measures.

A Notice of Availability for the Draft Environmental Impact Report (EIR) was sent to property owners within 300 feet of the Project site, tribes, agencies, and interested parties. The notice 45-day public comment review period started on October 28, 2022, and ended on December 12, 2022. During the 45-day comment period, the City received four (4) comment letters from the following interested parties (Exhibit (H)):

- South Coast Air Quality Management District (SCAQMD) – Commented regarding the analysis approach and modeling assumptions used in the air quality analysis. SCAQMD recommended a qualitative analysis of potential cumulative air quality and health risk impacts and questioned the fleet mix used in CalEEMod. SCAQMD requested clarification regarding the project's operational Health Risk Assessment (HRA) assumptions. Finally, SCAQMD stated that if permits from SCAQMD are required, this should be discussed in the Final EIR, and SCAQMD should be identified as a responsible agency.
- Lake Creek Industrial – Requested an explanation for the change in location of the proposed recycled water line and sewer line described in the Notice of Preparation (NOP) compared to how it was explained in the Draft EIR. This commenter also requested details for the recycled water line proposed by the project.
- Blum Collins & Ho, LLP on behalf of Golden State Environmental Justice Alliance (GSEJA) – The commenter alleges the Draft EIR does not comply with the requirements of CEQA and requests the Draft EIR be revised and recirculated. This commenter addresses multiple topics evaluated in the Draft EIR, but primarily focuses on air quality concerns, airport land use compatibility, general plan policy consistency, transportation, cumulative impact analysis, and alternatives.
- Adams Broadwell Joseph & Cardoz PC, Attorneys at Law on behalf of Californians Allied for a Responsible Economy (CARE CA) – This commenter alleges the Draft EIR does not comply with the requirements of CEQA and requests the Draft EIR be revised and recirculated. The commenter addresses several topics in the Draft EIR, but primarily focused on the information presented in the project description and environmental setting, air quality concerns, biological resources, noise impacts, and the findings necessary for land use entitlements. The commenter asserts the project description is not accurate or complete and does not identify the reasonably foreseeable uses of the Project site.

Responses to Comments were prepared and included in the Final EIR. None of the comments raised additional environmental concerns that have not been addressed in the EIR, constitute "significant new information" or meet any of the conditions in Section 15088.5 of the State CEQA Guidelines that would require recirculation of the EIR (Exhibit H). Per the Public Resources Code Section 21092.5, the City has to provide a written response to the commenting public agency at least ten days before the proposed certification date.

PUBLIC HEARING NOTICE:

A Notice of Public Hearing for the Planning Commission meeting was published in the local newspaper and sent to agencies and property owners within 300 feet of the project site. As of the writing and distribution of the staff report, staff has not received any other letters regarding this project.

RECOMMENDATION:

Recommend to the City Council adoption of Resolution 23-11 recommending certification of the Final Environmental Impact Report (SCH 2022010274), adoption of the Mitigation Monitoring and Reporting Program, and approval of the Specific Plan Amendment (SPA) 21-05267, Tentative Parcel Map 21-05086 (TPM-38259), Development Plan Review (DPR) 21-00005, to

facilitate the construction of a 764,753 square foot industrial warehouse distribution building, based on the findings and the Conditions of Approval.

BUDGET (or FISCAL) IMPACT: This project has no fiscal impact since the applicant bears all project costs.

Prepared by: Douglas Fenn, Contract Planner
Reviewed by: Patricia Brenes, Planning Manager

EXHIBITS:

- A. Resolution 23-11 Approving Conditions of Approval (Planning, Engineering, Public Works, Fire, Community Services, and Building & Safety)
- B. Location/Aerial Map
- C. PVCC-SP Land Use Map
- D. MARB/IPA ALUCP Map
- E. Existing and Proposed Modifications to Applicable PVCCSP Figures
- F. Tentative Parcel Map
- G. Project Plans (Site Plan, Fire Access Site Plan, Floor Plan, Building Elevations, Site Cross Sections, Conceptual Landscape/ Fence and Wall Plans, and Colors and Materials Sample Sheet)
- H. Final Environmental Impact Report (SCH: 2022010274), Mitigation Monitoring and Reporting Program, Associated Technical Studies, and Responses during NOA timeframe.

Due to the size of the files, the documents are available online at:

https://www.cityofperris.org/departments/development-services/planning/environmental-documents-for-public-review/-folder-333#docan1206_1313_479

Consent:
Public Hearing: X
Business Item:
Presentation:
Other:

EXHIBIT A

Reso 23-11 with Conditions of Approval
(Planning, Engineering, Public Works, Fire,
Community Services, and Building & Safety)

RESOLUTION NUMBER NO. 23-11

A RESOLUTION OF THE PLANNING COMMISSION OF THE CITY OF PERRIS, COUNTY OF RIVERSIDE, STATE OF CALIFORNIA, RECOMMENDING THAT THE CITY COUNCIL ADOPT ENVIRONMENTAL IMPACT REPORT (SCH NO. 2022010274) AND APPROVE SPECIFIC PLAN AMENDMENT 21-05267, TENTATIVE PARCEL MAP 21-05086 (TPM 38259), AND DEVELOPMENT PLAN REVIEW (DPR 21-00005) TO AMEND THE CIRCULATION PLAN OF THE PERRIS VALLEY COMMERCE CENTER SPECIFIC PLAN FOR THE REMOVAL OF TWO EXISTING PAPER STREETS AND MERGE 38 PARCELS INTO ONE (1) PARCEL TO FACILITATE THE CONSTRUCTION OF A 764,753-SQUARE-FOOT WAREHOUSE FACILITY ON A 35.63 ACRE SITE, LOCATED SOUTH OF HARLEY KNOX BOULEVARD BETWEEN PATTERSON AND NEVADA AVENUES, SUBJECT TO CONDITIONS OF APPROVAL AND BASED UPON THE FINDINGS NOTED HEREIN.

WHEREAS, the project applicant, Nicole Torsvet of Patterson Limited Partnership proposes to amend the Circulation Plan of the Perris Valley Commerce Center Specific Plan (“PVCCSP”) to vacate two existing unimproved streets, Nance Street and California Avenue, and consolidate 38 parcels into one (1) parcel to facilitate the construction and operation of a 764,753 square foot warehouse distribution facility on 35.63 acres located south of Harley Knox Boulevard between Patterson and Nevada Avenues;

WHEREAS, the applicant submitted: 1) Specific Plan Amendment (“SPA”) 21-05267 to vacate two paper/unimproved streets; 2) Tentative Parcel Map 21-05086 (“TPM 38259”) to merge the existing 38 parcels into one (1) parcel; and 3) Development Plan Review (“DPR”) 20-00005 for consideration of the site plan and building elevations (collectively the “Project”); and

WHEREAS, the proposed SPA 21-05267, TPM 38259, and DPR 20-00005 are considered a “Project” as defined by the California Environmental Quality Act (“CEQA”); and

WHEREAS, pursuant to CEQA and the State CEQA Guidelines (14 Cal. Code Regs. §15000 *et seq.*), the City is the lead agency for the Project, as it is the public agency with general governmental powers over the Project; and

WHEREAS, an Environmental Impact Report (“EIR”) (State Clearinghouse (SCH) No. 2022010274) was prepared for the Project, which includes, without limitation, SPA 21-05267, TPM 21-005086 (TPM-38259), DPR 21-00005, and was made available for public review and comments for a forty-five (45) day period in accordance with CEQA from November 4, 2022 to December 19, 2022; and

WHEREAS, the Airport Land Use Commission (“ALUC”) conducted a hearing on August 23, 2022, to consider the Project’s consistency with March Air Reserve Base/Inland Port Airport

Land Use Compatibility Plan (“MARB/IPA ALUCP”) is with the Airport Overlay Zone B2 (High Noise Zone), which prohibits residential uses and limits the number of people to an average of 100 people acres no more than 250 per single acre, and

WHEREAS the Planning Commission conducted a duly noticed public hearing on May 17, 2023, regarding the EIR and Project, at which time all interested persons were given full opportunity to be heard and to present evidence for the Planning Commission’s consideration, and after the public hearing and after consideration thereof, the Planning Commission recommended certification of the EIR and approval of the Project to the City Council; and

WHEREAS, before acting, the Planning Commission has heard, been presented with, and reviewed all of the information and data which constitutes the administrative record for the Project approval, including all oral and written evidence presented to the City by members of the public and City staff during all Project meetings and hearings; and

WHEREAS, all other legal prerequisites to adopting this Resolution have occurred.

NOW, THEREFORE, THE PLANNING COMMISSION OF THE CITY OF PERRIS does resolve as follows:

Section 1. The above recitals are all true and correct and incorporated herein by reference.

Section 2. Based upon the forgoing and all oral and written testimony made by members of the public and City staff (including without limitation the staff report and all exhibits/attachments) at the public hearing on March 17, 2023, the Planning Commission hereby finds:

1. An Environmental Impact Report (SCH 2022010274) has been completed in compliance with the California Environmental Quality Act (CEQA) Guidelines. The EIR concludes that all impacts have generally been reduced to less than significant or have been reduced to below the level of significance with the implementation of mitigation measures. The Planning Commission has fully considered the EIR and recommends that the City Council adopt the EIR. The Planning Commission recommends that the City Council find that the Project is consistent with and has been thoroughly assessed by the EIR and that this Project is anticipated explicitly in the EIR and is consistent with the purpose and intent of the EIR.
2. The City has complied with CEQA.
3. Determinations of the Planning Commission reflect the independent judgment of the City.

Section 3. Based upon the preceding, the Final Environmental Impact Report (SCH 2022010274), and all oral and written communication submitted by members of the public and

City staff to the Planning Commission on May 17, 2023, public hearing (including, but not limited to, all staff reports and supporting exhibits), the Planning Commission further finds the following:

Specific Plan Amendment 21-05267

- A. *The Specific Plan Amendment is consistent with the General Plan Land Use Map and applicable General Plan objectives, policies, and programs.*

The proposed amendment to the Circulation Plan of the Perris Valley Commerce Center Specific Plan (“PVCCSP”) is consistent with the General Plan in that the General Plan Land Use will remain consistent with the PVCCSP. It is located within the General Plan area designated as Planning Area 1. (North Commercial/Industrial) of the General Plan, which allows industrial and commercial opportunities due to the area’s proximity to the I-215 freeway and the proximity to March Global Port. As proposed, the project will be consistent with General Plan and will further the following General Plan Circulation Element goals:

Goal II (Circulation Element): A well-planned, designed, constructed, and maintained street and highway system that facilitates the movement of vehicles and provides safe and convenient access to surrounding developments.

Goal V (Circulation Element): Efficient goods movement.

Policy V.A (Circulation Element): Require Street abutting properties in the General Industrial (GI) and Light Industrial (LI) Zone to conform to standard specifications for industrial collector streets to accommodate the movement of heavy trucks. Provide adequate off-street loading area for all manufacturing land uses.

- B. *The Specific Plan Amendment provides adequate text and diagrams to address the following issues in detail adequately:*

1. *The distribution, location, and extent of the land use of land, including open space, within the area covered by the Plan.*

The proposed Specific Plan Amendment will not change the land use designations of the project site, consisting of GI – General Industrial and LI – Light Industrial. The GI and LI land use designations are intended for manufacturing and light industrial uses. The proposed industrial warehouse distribution building is consistent with the intent of the underlying designations. The Specific Plan Amendment is limited to vacating Nance Street and California Avenue, paper/unimproved streets, and will have no impacts on the surrounding uses. The project will function properly with respect to land use, circulation, drainage, and water and sewer issues.

2. *The proposed distribution, location, and extent and intensity of major components of public and private transportation, sewage, water, drainage, solid waste disposal, energy, and other essential facilities proposed to be located within the area covered by the Plan and needed to support the land use described in the Plan.*

Eastern Municipal Water District (EMWD) prepared a Water Supply Assessment for this project. It determined that it will be able to provide adequate water supplies to meet the potable water demand for this project. All improvements for sewage, water, drainage, solid waste disposal, energy, and other essential facilities will be subject to approval by the City and EMWD.

3. *Standards and criteria by which development will proceed and standards for the conservation, development, and utilization of natural resources, where applicable.*

There are no natural resources on the property or designated conservation areas. The project will comply with all applicable mitigation measures required by the EIR. The project has been designed to comply with Chapter 19.69 – Parking and Loading Standards of the Zoning Code. As well, the project has been designed to comply with the following Chapters of the PVCCSP:

- Chapter 4 – On-Site Design Standards and Guidelines
- Chapter 5 – Off Site Design Standards and Guidelines
- Chapter 6 – Landscape Standards and Guidelines
- Chapter 8 – Industrial Design Standards and Guidelines

4. *A program of implementation measures, including regulation, programs, public works projects, and financing measures necessary to carry out the provisions in paragraphs 1, 2, and 3 above.*

Specific Plan Amendment 21-05267 proposes to amend the Circulation Plan of the PVCCSP to remove two existing paper streets to facilitate the proposed industrial warehouse project and commercial center. It will not impact existing land uses, including open space within the PVCCSP. The following maps have been revised to reflect the removal of the street and land use change from the PVCCSP:

- Figure 3.0-1 Circulation Plan Map
- Figure 3.0-4 Mass Transit Routes
- Figure 3.0-5 Trails System Map
- Figure 3.0-7 Existing EMWD Water Map
- Figure 3.0-8 Existing EMWD Sewer Map
- Figure 3.0-9 Existing EMWD Recycled Water Map
- Figure 3.0-12 Existing Natural Gas Map
- Figure 3.0-13 Existing Electrical Map
- Figure 3.0-14 Existing Telephone Map
- Figure 3.0-15 Electrical Cable TV Map

Chapter 13 – Implementation and Administrative Process of the PVCCSP establishes a program of implementation measures, including regulation, programs, and financing measures necessary to carry out the provisions contained in paragraphs 1, 2, and 3 above. Chapter 3 – Infrastructure Plan of the PVCCSP outlines public works projects within the PVCCSP with text and diagrams intended to guide and support development in the PVCCSP. As noted above, the Project requires the removal of two paper streets detailed in several of the Figures contained within Chapter 3 to facilitate the proposed vacation of the streets that will occur in connection with the proposed industrial warehouse project.

Tentative Parcel Map 21-05086 (TPM 38259)

1. *The proposed map is consistent with the applicable General and Specific Plans.*

The Project proposes a Tentative Parcel Map to consolidate 38 parcels into one (1) 35.63-acre parcel. The map is consistent with the minimum lot size of 15,000 square feet, approximate lot width of 779 feet, and lot depth of 1,284 feet required in the General Industrial (GI) and Light Industrial (LI). The map will facilitate the construction and operation of a 764,753-square-foot warehouse facility. The project is located within the General Plan area designated as Planning Area 1. (North Commercial/Industrial) of the General Plan, which allows industrial and commercial opportunities due to the area's proximity to the I-215 freeway and the proximity to March Global Port. As proposed, the project will be consistent with General Plan.

The site is physically suitable for the type and density of the proposed development.

As noted above, the Project proposes a Tentative Parcel Map to consolidate 38 parcels into one (1) 35.63-acre parcel. The Project has been designed to be consistent with all applicable Code requirements for industrial projects in the GI and LI and Zones of the PVCCSP, including lot coverage, floor area ratio, height, setbacks, landscaping, and parking, as noted in the staff report.

2. *The map's design or the type of improvements will not cause substantial environmental damage or unavoidably injure fish, wildlife, or their habitat.*

The potential environmental impacts associated with the Project were evaluated in the Final Environmental Impact Report (SCH 2022010274). It has been determined that all possible effects of the Project on aesthetics, air quality, biological resources, cultural resources, energy, geology and soil, greenhouse gas emissions, hazards, noise, transportation, and tribal cultural resources will be reduced to less than significant levels with implementation of mitigation measures.

3. *The map's design or the type of improvements will not cause serious public health problems.*

The EIR prepared for the Project concludes that all impacts related to aesthetics, air quality, biological resources, cultural resources, energy, geology and soil, greenhouse gas emissions, hazards, noise, transportation, and tribal cultural resources have been reduced to less than significant or have been reduced to below the level of significance with the implementation of mitigation measures.

Development Plan Review 21-00005

1. *The location, size, design, density, and intensity of the proposed development and improvements are consistent with the City's General Plan, any applicable Specific Plans, the purposes and provisions of this Title, the purposes of the zone in which the site is located, and the development policies and standards of the City.*

The Project proposes the construction of a 764,753-square-foot industrial warehouse on 35.63 acres in the GI and LI Zones of the PVCCSP, which allows for “light industrial uses and related activities including manufacturing, warehouse and distribution, assembly of non-hazardous material and retail related to manufacturing.” The location, size, design, density, and intensity of the proposed development and improvements are consistent with the City's General Plan, the PVCCSP, the purposes and provisions of the Perris Municipal Code, the purposes of the Zones in which the site is located, and the development policies and standards of the City.

2. *The subject site is physically suitable, including but not limited to parcel size, shape, access, and availability of utilities and services, for the type of development proposed.*

The industrial components of the Project are in compliance with the development standards of the underlying zones. Adequate access, utilities, and services are provided on-site. The proposed Project will not be detrimental to public health, safety, or welfare or materially injurious to properties or improvements in the vicinity.

3. *The proposed development and the conditions under which it would be operated or maintained are compatible with abutting properties. They will not be detrimental to the public health, safety, or welfare or materially injurious to properties or improvements in the vicinity.*

The proposed Project will not be detrimental to public health, safety, or welfare or materially injurious to properties or improvements in the vicinity. The traffic study for the project concluded that all the study area intersections are anticipated to operate at acceptable levels of service after the Project is operating.

The Project proposes an architecturally enhanced industrial warehouse building with varying roofline angles and heights, steel canopy awnings, bronze glazing building elements, and other accents. Colors on the façades range from different hues of grey, darker colors, and white accents meet the development standards of

the PVCCSP and the General Industrial (GI) and Light Industrial (LI) Zones. The proposed screen walls and landscaping ensure visual relief and an attractive environment for the public's enjoyment.

Section 4. Based upon the preceding, the Environmental Impact Report (SCH: 2022010274), and all oral and written communication submitted by members of the public and City staff to the City Council on May 17, 2023, public hearing (including, but not limited to, all staff reports and supporting exhibits), the Planning Commission recommends that the City Council approve Specific Plan Amendment 21-05267, Tentative Parcel Map No. 21-05086. (TPM 38259), and Development Plan Review 20-00005, subject to the Mitigation Monitoring and Reporting Program and Conditions of Approval attached to this Resolution as Attachments 1 and 2.

Section 5. The Planning Commission declares that should any provision, section, paragraph, sentence, or word of this Resolution be rendered or declared invalid by any court of competent jurisdiction or by reason of any preemptive legislation, the remaining provisions, sections, paragraphs, sentences, and words of this Resolution shall remain in full force and effect.

Section 6. The Chairman shall sign this Resolution, and the Chairperson shall certify the adoption of this Resolution.

ADOPTED, SIGNED, and APPROVED this 17th day of May 2023.

CHAIRPERSON, PLANNING COMMISSION

ATTEST:

Secretary, Planning Commission

STATE OF CALIFORNIA)
COUNTY OF RIVERSIDE)
CITY OF PERRIS)

I, Patricia Brenes, SECRETARY OF THE PLANNING COMMISSION OF THE CITY OF PERRIS, CALIFORNIA, DO HEREBY CERTIFY that the foregoing Resolution Number No. 23-11 was duly and regularly adopted by the Planning Commission of the City of Perris at a regular meeting held on the 17th day of May 2023, by the following called a vote:

AYES:

NOES:

ABSENT:

ABSTAIN:

Secretary, Planning Commission

- Attachments:**
1. Conditions of Approval (Planning, Engineering, Public Works, Community Services, Fire, Building and Safety)
 2. Mitigation Monitoring and Reporting Program
Due to the size of the files, the documents are available online at:
https://www.cityofperris.org/departments/development-services/planning/environmental-documents-for-public-review/-folder-333#docan1206_1313_479

ATTACHMENT 1

Conditions of Approval (Planning,
Engineering, Public Works, Community
Services, Fire, Building and Safety)

**CITY OF PERRIS
DEVELOPMENT SERVICES DEPARTMENT
PLANNING DIVISION**

CONDITIONS OF APPROVAL

**SPA 21-05267, TPM 21-005086 (TPM-38259),
DPR 21-00005**

May 17, 2023

PROJECT: Specific Plan Amendment (SPA) 21-05267, Tentative Parcel Map 21-05086 (TPM-38259), Development Plan Review (DPR) 21-00005 – A proposal to consider the following entitlements to facilitate the construction of a 764,753 square-foot industrial warehouse facility: 1) Specific Plan Amendment to vacate the California Avenue and Nance Street, planned and unimproved streets, from the Circulation Plan in the Perris Valley Commerce Center Specific Plan (PVCCSP); 2) Tentative Parcel Map to consolidate 38 existing parcels into one (1) 35.63 acre-parcel; 3) Development Plan Review for the site plan and building elevations. The 35.63-acre project site is located south of Harley Knox Boulevard between Patterson Avenue and Nevada Avenue, in the GI - General Industrial and LI - Light Industrial Zones. (APNs: 314-153-015 through -040, 314-153-042, 314-153-044, -046, -048, 314-160,005 through -012, and 314-160-033. Applicant: Nicole Torsvet, Patterson Limited Partnership.

GENERAL CONDITIONS:

- 1 **Approval Period for Development Plan Review 21-00005,** The Development Plan Review processed in conjunction with the Tentative Parcel Map shall expire in two years from the City Council's final action for consistency with the time limits of the map. Within two years, the applicant shall demonstrate the beginning of substantial construction as approved, which shall thereafter be diligently pursued to completion or substantial utilization. If this does not occur, a maximum of six (6) one-year extensions may be requested for consistency with the related Tentative Parcel Map A written request for extension shall be submitted to the Planning Division at least thirty (30) days prior to the initial (and any subsequent extension) expiration of the Development Plan Review.
- 2 **Approval Period for Tentative Parcel Map (TPM 38259).** In accordance with the Subdivision Map Act, the recordation of the final map shall occur within two (2) years from the City Council approval unless the State of California grants an automatic extension. The applicant may apply for a maximum of six (6) one-year extensions to permit additional time to record the final map. A written request for an extension shall be submitted to the Planning Division at least thirty (30) days prior to the initial (and subsequent extensions) expiration of the Tentative Parcel Map approval.
- 3 **Mitigation Monitoring and Reporting Program.** The project shall comply with all provisions of the adopted Mitigation Monitoring and Reporting Program (MMRP). The Mitigation Monitoring and Reporting Program (MMRP) for Environmental Impact Report (SCH: 2022010274). It shall be implemented in accordance with the timeline, reporting, and monitoring intervals listed.
- 4 **Municipal Code and Specific Plan Compliance.** The project shall conform to the General Industrial (GI) and Light Industrial (LI) Zone standards of the Perris Valley Commerce Center Specific Plan (PVCCSP) and Title 19 of the Perris Municipal Code.

- 5 **Future Obligation of Buyers and Lessees.** All future buyers and lessees shall be informed of their obligation to comply with these Conditions of Approval. The applicant shall provide a copy of these conditions and inform the buyer or lessee of their obligation to maintain compliance with all local and City ordinances, including but not limited to an annual fire inspection and maintenance of a City business license.
- 6 **City Ordinances and Business License.** The subject business shall maintain compliance with all local and City Ordinances, including but not limited to an annual fire inspection and maintenance of a City business license.
- 7 **Expansion of Use.** All expansion of the site and its use shall occur with subsequent reviews and approvals by the Planning Division.
- 8 **Conformance to Approved Plans.** Development of the project site, building elevations, and conceptual landscaping shall conform substantially to the plans approved by the Planning Commission on **May 17, 2023**, or as amended by these conditions. Any deviation shall require appropriate Planning Division review and approval.
- 9 **ADA Compliance.** The project shall conform to all disabled access requirements in accordance with the State of California, Title 24, and the Federal Americans with Disabilities Act (ADA).
- 10 **Rooftop Solar.** The project does not propose rooftop solar panels at this time. However, if the project were to propose solar rooftop panels in the future, the applicant/developer shall prepare a solar glare study that analyzes glare impacts, and the Airport Land Use Commission and March Air Reserve Base shall review this study.
- 11 **Planning Division.** All Planning Division Conditions of Approval shall be reproduced in the construction and grading plans.
- 12 **City Engineer Conditions.** The project shall adhere to the requirements of the City Engineer as indicated in the attached Engineering Conditions of Approval dated **March 13, 2023**. On and off-site improvement plans shall be submitted for review and approval by the City Engineer.
- 13 **Fire Marshall Conditions.** The project shall comply with all requirements of the Fire Marshall in the memo dated **December 28, 2022**.
- 14 **Building Official/Fire Marshal.** The proposed project shall adhere to all requirements of the Building Official/Fire Marshal. Fire hydrants shall be located on the project site pursuant to the Building Official and the approved Fire Access Plan. Water, gas, sewer, electrical transformers, power vaults, and separate fire/water supply lines (if applicable) must be shown on the final set of construction plans pursuant to the requirements of the Building Official. All Conditions of Approval shall be included in the building plans. See City of Perris website, Office of the Fire Marshal, for examples and relevant information for access and underground plan available at: <http://www.cityofperris.org>.
- 15 **Building Conditions.** The project shall adhere to the requirements of the Building Department as indicated in the attached Conditions of Approval dated **May 10, 2021**.
- 16 **Public Works Conditions.** The project shall adhere to the requirements of the Public Works Administration Department as indicated in the attached Conditions of Approval dated **December 5, 2022**.
- 17 **Fire Conditions.** The Following conditions shall apply to the project:

- a. The project shall comply with all requirements set forth by the California Code of Regulations Title 24 Parts 1-12 respectively.
- b. The adopted edition of the California Code of Regulations, Title 24, Parts 1 through 12, and the Perris Municipal Code shall apply at the time the architectural plans are submitted for construction permits.
- c. Prior to the to the issuance of a grading permit, evidence of sufficient fire flow of 4,000 GPM for 4- hours shall be provided to the City of Perris. The City of Perris Building and Fire Marshal Water Available/Fire Flow Form shall be utilized.
- d. A fire department access road complying with the CFC, Chapter 5 and the approved fire department access plans shall be installed prior to building construction.
- e. All required fire hydrants shall be installed and operational prior to building construction. All fire hydrants shall remain operational during construction.
- f. All required fire hydrants shall be readily visible and immediately accessible. A clear space of not less than 3 feet shall be maintained at all times.
- g. The private underground fire-line system shall be a looped design.
- h. The private underground fire-line system shall have indicating sectional valves for every five (5) appurtenances.
- i. A minimum of two points of connection to public water shall be provided for the private fire-line water.
- j. The Fire Department Connection (FDC) shall be located within 100 feet of a public fire hydrant. The fire hydrant shall be on the same side of the street. A vehicle access roadway/approach shall not be placed between the FDC and fire hydrant.
- k. Prior to construction a temporary address sign shall be posted and clearly visible from the street.
- l. The permanent building address shall be provided and either internally or externally lit during hours of darkness. The address shall be clearly visible from the street fronting the property and comply with California Fire Code Section 505.1 for size and color.
- m. City of Perris approval shall be obtained prior to the storage and/or use of hazardous materials as defined by the California Fire Code.
- n. The building shall be provided with an automatic fire sprinkler system in accordance with NFPA 13. Construction plans shall be submitted for review and approval to the City of Perris prior to installation.
- o. Prior to building final, the building shall be provided with a Knox Lock key box located no more than 7 feet above the finished surfaced and near the main entrance door.
- p. Prior to building final the building shall be provided with an emergency radio communication enhancement system. The emergency radio communication enhancement system shall meet the requirements of CFC § 510 and all applicable subsections. The system shall be installed and inspected by the City of Perris Building Department before the Certificate of Occupancy is issued. The requirement can be waived by the Fire Marshal if the building is evaluated by an Emergency Radio Communication Specialist license by FCC, who certifies the building meets the emergency communications

capability as specified by the California Fire Code § 510. The certification shall be in the form of a written report which outlines the analysis used in determining the building meets the emergency communications without an enhancement system.

- 18 **Val Verde Unified School District.** The proposed subdivision shall adhere to the standard requirements and mitigation fees established by the Val Verde Unified School District.
- 19 **Indemnification.** The developer/applicant shall indemnify, protect, defend, and hold harmless the City and any agency or instrumentality thereof and/or any of its officers, employees, and agents from any and all claims, actions, or proceedings against the City or any agency or instrumentality thereof, or any of its officers, employees, and agents, to attack, set aside, void, annul, or seek monetary damages resulting from approval of the City, or any agency or instrumentality thereof, advisory agency, appeal board or legislative body including actions approved by the voters of the City concerning **SPA 21-05267, TPM 21-005086 (TPM-38259), and DPR 21-00005**. The City shall promptly notify the applicant of any claim, action, or proceeding for which indemnification is sought and shall cooperate fully in defense of the action.
- 20 **Southern California Edison (SCE).** The developer/owner shall contact the Southern California Edison SCE area service planner (951-928-8323) to complete the required forms before construction. Grade permit shall be issued once the City Engineer receives a letter from SCE indicating that electrical service will be placed underground.
- 21 **Signage.** The project approval does not include signage. All monument signage is required to include the Perris Valley Commerce Center logo (per PVCCSP Chapter 4.2.5). Any proposed wall or monument sign will require a sign application and shall be reviewed and approved by the Planning Division prior to building permit issuance.
- 22 **Waste Hauling and Disposal.** The project shall use only the City-approved waste hauler for all construction and other waste disposal.
- 23 **Graffiti and Property Maintenance.** The project shall comply with the Perris Municipal Code Chapter 7.42 regarding Property Maintenance. The site shall be maintained graffiti-free state at all times. Graffiti located on site shall be removed within 48 hours. Graffiti shall be painted over in panels and not patches. In addition, it will match the color of the wall or material surface. Furthermore, the applicant shall apply an anti-graffiti coating on the walls.
- 24 **On-site & Off-site Utilities.** All utilities attached to buildings, including meters and utility boxes, shall be painted to match the wall of the building to which they are affixed. These facilities shall also be screened from the public right-of-way by landscaping.
- 25 **Performance Standards.** The applicant shall comply with all Performance Standards listed in Chapter 19.44.070 of the Perri Municipal Code.
- 26 **Utilities.** If applicable, all utilities such as cable TV and electrical distribution lines (including those which provide direct service to the project site and/or currently exist along public right-of-way) adjacent to the site shall be placed underground, except for electrical utility lines rated at 65kv or larger. All utility facilities attached to buildings, including meters and utility boxes, shall be painted to match the wall of the building to which they are affixed. These facilities shall also be screened from the public right-of-way by landscaping.
- 27 **Screening of Roof-Mounted Equipment.** Proper screening shall prevent public views of all HVAC equipment and roof-mounted equipment. Also, all vent pipes and similar devices shall be painted to match the building.

Conditions of Approval

- 28 **Mechanical Equipment.** All mechanical equipment, including air conditioning units, pool equipment, etc., shall be screened from the public right-of-way by a view obscuring fence, wall, or landscaping to the satisfaction of the Planning Division.
- 29 **Downspouts.** Exterior downspouts are not permitted on building elevations facing the public right of way. Interior downspouts are required for these elevations.
- 30 **Energy Conservation.** To improve local air quality, the applicant shall comply with the energy-conservation features in the project (as feasible) per the FEIR and Design Guidelines. An accounting of the project's energy conservation measures shall be submitted to the Building Division prior to the application for building permits.
- 31 **Glazing.** Highly reflective glass shall not be used for architectural elevations.
- 32 **Roof Parapets.** The height of the roof parapet shall fully screen any roof-mounted equipment. All vent pipes and similar devices shall be painted to match the building.
- 33 **Payment of Department of Fish and Wildlife Fee.** Within five (5) days of City Council approval, the applicant shall file a Notice of Determination of the Riverside County Clerk and submit appropriate payment of fees in accordance with Section 753.5 (Title 14) of the California Code of Regulations; no project shall be operative, vested, or final until the filing fees have been paid.
- 34 **Preliminary Water Quality Management Plan (PWQMP).** A Preliminary WQMP was prepared for the proposed project site. All PWQMPs were determined to be in substantial compliance, in concept, with the 2012 Riverside County WQMP Manual requirements. The following conditions apply:
 - a. The development shall be subject to all provisions of City of Perris Ordinance Number 1194, which establishes stormwater/urban runoff management and discharge controls to improve water quality and comply with federal regulations and any subsequent amendments, revisions, or ordinances pertaining thereto.
 - b. The structural BMPs selected for this project have been approved in concept. The owner shall submit a final WQMP, including plans and details providing the elevations, slopes, and other details for the proposed structural BMPs, including two bioretention basins, a self-retaining landscape, and a covered trash enclosure. The Public Works Department shall review and approve the final addendum WQMP text, plans, and details.
- 35 **Construction Practices.** To reduce potential traffic, noise, and air quality impacts, the mitigation measures listed in Final Environmental Impact Report (SCH: 2022010274) and Reporting Plan (MMRP) shall be listed and included with the "General Notes" on the construction drawings and implemented in accordance with the timeline, reporting and monitoring intervals listed in the MMRP.
- 36 **Off-Site Tree Planting or Funding.** To promote the City's tree planting initiative currently underway to make Perris GREEN providing positive benefits to the local environment from air quality to shading, the developer shall plant one 24-inch box tree per 5,000 square feet of building size to include irrigation lines and controllers at an off-site location to be determined by the City (i.e., City right-of-way, parks, etc.) to provide funding equivalent to such cost the discretion of the City prior to issuance of the building permit.
- 37 **Trash Enclosures.** Trash enclosures shall be screened with landscaping (vines and shrubs) and provide decorative solid trellis cover per the development plans presented to the

Planning Commission.

- 38 **Construction Practices.** To reduce potential noise and air quality nuisances, the following items shall be listed as "General Notes" on the construction drawings:
- a. Construction activity and equipment maintenance are limited to weekday hours between 7:00 a.m. and 7:00 p.m. Construction may not occur on weekends or State holidays without the prior consent of the Building Official. Non-noise-generating activities (e.g., interior painting) are not subject to these restrictions.
 - b. Construction routes are limited to City of Perris designated truck routes.
 - c. Water trucks or sprinkler systems shall be used during clearing, grading, earth moving, excavation, transportation of cut or fill materials, and construction phases to prevent dust from leaving the site and to create a crust after each day's activities cease. At a minimum, this would include wetting down such areas in the later morning and after work is completed for the day and whenever wind exceeds 15 miles per hour.
 - d. A person or persons shall be designated to monitor the dust control program and to order increased watering as necessary to prevent the transport of dust off-site. The name and telephone number of such persons shall be provided to the City. Also, a board shall be placed at the subject site to include a person and phone number for the public to call in case of dirt and dust issues.
 - e. Project applicants shall provide construction site electrical hook-ups for electric hand tools, such as saws, drills, and compressors, to eliminate the need for diesel-powered electric generators or provide evidence that electrical hook-ups at construction sites are not practical or prohibitively expensive.
- 39 **Property Maintenance.** The project shall comply with provisions of the Perris Municipal Code 7.06 regarding Landscape Maintenance and Chapter 7.42 regarding Property Maintenance. In addition, the project shall comply with the one-year landscape maintenance schedule.
- 40 **Riverside County Airport Land Use Commission.** The following conditions shall be satisfied in accordance with the Airport Land Use Commission (ALUC) Development Review case file ZAP1538MA22:
- a. Any new outdoor lighting installed shall be hooded or shielded to prevent the spillage of lumens or reflection into the sky. Outdoor lighting shall be downward facing.
 - b. The following uses/activities are not included in the proposed project and shall be prohibited at this site:
 - i. Any use which would direct a steady light or flashing light of red, white, green, or amber colors associated with airport operations toward an aircraft engaged in an initial straight or circling climb following takeoff or toward an aircraft engaged in a straight or circling final approach toward a landing at an airport, other than a DOD or FAA-approved navigational signal light or visual approach slope indicator.
 - ii. Any use which would cause sunlight to be reflected towards an aircraft engaged in an initial straight or circling climb following takeoff or towards an aircraft engaged in a straight or circling final approach towards a landing at an airport.

- iii. Any use which would generate smoke or water vapor or which would attract large concentrations of birds, or which may otherwise affect safe air navigation within the area. (Such uses include landscaping utilizing water features, aquaculture, production of cereal grains, sunflower, and row crops, composting operations, wastewater management facilities, artificial marshes, trash transfer stations that are open on one or more sides, recycling centers containing putrescible wastes, construction and demolition debris facilities, fly ash disposal, and incinerators).
 - iv. Any use which would generate electrical interference that may be detrimental to the operation of aircraft and/or aircraft instrumentation.
 - v. Children's schools, daycare centers, libraries, hospitals, skilled nursing and care facilities, congregate care facilities, places of assembly (including but not limited to places of worship and theaters), buildings with more than 3 aboveground habitable floors, and critical community infrastructure facilities.
 - vi. Highly noise-sensitive outdoor nonresidential uses. Examples of noise-sensitive outdoor nonresidential uses that are prohibited include but are not limited to, major spectator-oriented sports stadiums, amphitheaters, concert halls, and drive-in theaters.
 - vii. Other Hazards to flight.
- c. The attached "Notice of Airport in Vicinity" shall be provided to all prospective purchasers and occupants of the property and be recorded as a deed notice.
 - d. The project has been conditioned to utilize underground detention systems, which shall not contain surface water or attract wildlife. Any other proposed basin would require review and approval by the ALUC. Any proposed stormwater basins or facilities shall be designed and maintained to provide for a maximum 48-hour detention period following the design storm and remain dry between rainfalls. Vegetation in and around the basins that would provide food or cover for birds would be incompatible with airport operations and shall not be utilized in project landscaping. Trees shall be spaced so as to prevent large expanses of the contiguous canopy when mature. Landscaping in and around the basin(s) shall not include trees or shrubs that produce seeds, fruits, or berries.

Landscaping in the detention basin, if not rip-rap, should be in accordance with the guidance provided in ALUC "LANDSCAPING NEAR AIRPORTS" brochure, and the "AIRPORTS, WILDLIFE AND STORMWATER MANAGEMENT" brochure available at RCALUC.ORG which list acceptable plants from Riverside County Landscaping Guide or other alternative landscaping as may be recommended by a qualified wildlife hazard biologist.

A notice sign, in a form similar to that attached hereto, shall be permanently affixed to the stormwater basin with the following language: "There is an airport nearby. This stormwater basin is designed to hold stormwater for only 48 hours and not attract birds. Proper maintenance is necessary to avoid bird strikes". The sign will also include the er or other contact information of the person or entity responsible for the stormwater basin.

- e. March Air Reserve Base must be notified of any land use having an electromagnetic radiation component to assess whether a potential conflict with Air Base radio

- communications could result. Sources of electromagnetic radiation include radio wave transmission in conjunction with remote equipment, inclusive of irrigation controllers, access gates, etc.
- f. Noise attenuation measures shall be incorporated into the design of the structure's office and retail areas to ensure that interior noise levels from aircraft operations are at or below 45 CNEL.
 - g. The project has been evaluated for a 769,668 square feet warehouse building, consisting of 749,668 square feet of warehouse area, 10,000 square feet of first-floor office area, and 10,000 square feet of second-floor office mezzanines. Any increase in building area, change in use to any higher intensity use, change in building location, or modification of the tentative parcel map lot lines and areas will require an amended review to evaluate consistency with the ALUCP compatibility criteria at the discretion of the ALUC Director.
 - h. The project does not propose rooftop solar panels at this time. However, if the project were to propose solar rooftop panels in the future, the applicant/developer shall prepare a solar glare study that analyzes glare impacts, and this study shall be reviewed by the Airport Land Use Commission and March Air Reserve Base
 - i. The Federal Aviation Administration has conducted aeronautical studies of the proposed project (Aeronautical Study No. Aeronautical Study No. 2022-AWP-12523-OE thru 2022-AWP-12526-OE) and has determined that neither marking nor lighting of the structure(s) is necessary for aviation safety. However, if marking and/or lighting for aviation safety is accomplished on a voluntary basis, such marking and/or lighting (if any) shall be installed in accordance with FAA Advisory Circular 70/7460-1 M and shall be maintained in accordance therewith for the life of the project.
 - j. The proposed structures shall not exceed the prescribed height of 45 feet above the ground and a maximum elevation at the top point of 1,539 above mean sea level.
 - k. The maximum height and top point elevation specified above shall be amended with further review by the Airport Land Use Commission and the Federal Aviation Administration, provided; however, that structure height or elevation reduction shall not require further review by the Airport Land Use Commission. The specific coordinates, frequencies, and power shall be amended with further review by the Federal Aviation Administration.
 - l. Temporary construction equipment used during actual construction of the structure(s) shall be at most the prescribed heights as identified in the aeronautical study unless separate notice is provided to the Federal Aviation Administration through the Form 7460-1 process.
 - m. Within five (5) days after construction of the structure reaches its greatest height, FAA Form 7460-2 (Part II), Notice of Actual Construction or Alteration, shall be completed by the project proponent or his/her designee and e-filed with the Federal Aviation Administration. (Go to <https://oeaaa.faa.gov> for instructions.) This requirement is also applicable in the event the project is abandoned, or a decision is made not to construct the applicable structure.

TPM 38259 - FINAL MAP RECORDATION

41 **Application.** The Final Map application shall be submitted to the City Engineering

Conditions of Approval

Department with payment of appropriate fees for review and approval concurrently with the application to the City Engineer. The Final Map application shall include all necessary road dedications, appropriate easements, and street vacations.

- 42 **Map Recordation.** Prior to the recordation of the Final Map, the developer shall obtain the following clearances, approvals or actions:
- a. Verification from the Planning Division that all pertinent conditions of approval have been met, as mandated by the Perris Municipal Code.
 - b. The landowner shall convey an avigation easement to the March Inland Port Airport Authority. Contact the March Joint Powers Authority at (951) 656-7000.
 - c. Any other required approval from an outside agency.

PRIOR TO THE ISSUANCE OF GRADING PERMITS

- 43 **Precise Grading Plans.** Precise grading plans shall be submitted to the City Engineer for review and approval. Grading plans shall be consistent with approved development plans.
- 44 **Traffic Control Plan.** A Traffic Control Plan shall be submitted for approval to the City Engineer.
- 45 **Southern California Edison.** Prior to the issuance of grading permits, the applicant shall contact the Southern California Edison (SCE) area service planner to complete the required forms prior to the commencement of construction.
- 46 **Final Water Quality Management Plan (FWQMP).** Prior to the issuance of grading permits, an FWQMP is required to be submitted. To mitigate impacts related to pollutant loading to receiving waters and/or increased erosion/siltation resulting from the long-term operation of the project, the applicant shall develop, receive approval from the City, and implement an FWQMP. The FWQMP shall contain measures that will effectively treat all pollutants of concern and hydrologic conditions of concern, consistent with the Preliminary WQMP and developed in compliance with the MS4 permit. The FWQMP shall specifically identify pollution prevention, source control, treatment control measures, and other Best Management Practices (BMPs) that shall be used on-site to control predictable pollutant runoff to reduce impacts to water quality to the maximum extent practicable. The FWQMP shall substantially comply with site design, source control, and treatment control BMPs proposed in the approved Preliminary Water Quality Management Plan (PWQMP).
- 47 **Planning Clearance.** The applicant shall first obtain clearance from the Planning Division to verify that all pertinent conditions of approval have been met.

PRIOR TO THE ISSUANCE OF BUILDING PERMITS

- 48 **March Air Reserve Base and Perris Valley Airport.** Prior to building permit issuance, in accordance with the conditions of approval by the Airport Land Use Commission (ALUC) letter dated August 23, 2022, the conditions of approval enumerated in the conditional approval letter shall be implemented to address the project's location within Airport Influence Area.
- 49 **Building Plans.** All Planning, Public Works, and Engineering Conditions of Approval shall be copied onto the approved building plans. Such conditions shall be annotated, directing the receiver to the sheet and detail(s) indicating satisfaction of the conditions. Also, the Mitigation and Monitoring Reporting Plan (MMRP) shall be listed and included with the "General Notes" on the construction drawings, and implemented in accordance with the timeline, reporting and monitoring intervals listed in the MMRP.

- 50 **Final Parcel Map Submittal.** Prior to the issuance of the first building permit, Tentative Parcel Map 38259 shall be submitted for Final Map approval to the City Engineering Department and be recorded with the County of Riverside, with proof of recording provided to the City Planning Division and Engineering Division. The Final Map shall conform substantially to the approved Tentative Map.
- 51 **Landscaping Plans.** Prior to the issuance of building permits, three (3) copies of Construction Landscaping and Irrigation Plans shall be submitted to the Planning Division for approval, accompanied by the appropriate filing fee. The plans shall be prepared by a California-registered landscape architect and conform to the requirements of Chapter 19.70 of the Municipal Code. The location, number, genus, species, and container size of the plants shall be shown. The following treatments, consistent with the conceptual landscape plan or as conditioned herein, are required:
- a. **Accent Landscaping.** Large trees (24" to 36" box) shall be included in the landscape design at all driveway entrances to the project site.
 - b. **Passenger Vehicle Parking Areas.** A minimum of 30% of trees shall be a 36-inch box or larger in passenger vehicle parking areas. Also, a minimum of one 24-inch box tree per six (6) parking stalls shall be provided.
 - c. **Conceal parking lot area.** All parking areas along the street frontages shall be screened by a minimum 36-inch-high shrub border using a double-row of 5-gallon shrubs at 3.6 feet off center.
 - d. **Street Trees.** All street trees within the public right of way shall be 24-inch box size or larger and planted a maximum of 30 feet on center within the parkway.
 - e. **Employee Amenity Areas.** The outdoor employee break area shall be landscaped to include shade trees and shade structures architecturally similar in colors and materials to the warehouse building.
 - f. **Enhanced Pavement.** Decorative pavement treatments (accent colors, textures, and patterns) shall be used for all driveway entrances and pedestrian pathways.
 - g. **BMPs for Water Quality.** All BMPs (vegetated swales, detention basins, etc.) shall be indicated on the landscape plans with appropriate planting and irrigation.
 - h. **Shade Tree.** The project shall provide shade trees throughout the parking lot per the Development Code and landscape standards of the PVCCSP.
 - i. **Water Conservation.** Rain-sensing override devices and soil moisture sensors shall be required on all irrigation systems. Landscaping shall comply with Zoning Code Chapter 19.70 (www.cityofperris.org) for mandated water conservation.
 - j. **Maintenance.** All landscaping shall be maintained in a viable growth condition.
 - k. **Site Plan Requirements.** The following shall be shown on the building plan check set for Planning staff review and approval:
 - a. **Parking Stalls.** Parking stalls for passenger vehicles shall be striped in accordance with Chapter 19.69.030C.5b of the Zoning Code (double striping).
 - b. **Parking Lot.** Evergreen trees shall be planted every 6 parking spaces throughout the parking lots for passenger vehicles on the north and west sides of the site.
 - c. **Charging Stations.** The applicant shall install and install the Electric Vehicle charging

Conditions of Approval

stations for the EV parking stalls that are depicted on the site plan and must accommodate light-duty vehicles, and the station locations and specifications shall be included on the building plans.

- 52 **Screen Walls and Fencing.** Decorative screen walls shall screen views into truck courts from the public rights of way (Patterson and Nevada Avenues) and adjacent uses. Plans and details for the screen walls shall be included in the landscape plan check submittal package for review and approval by the Planning Division. Any changes to the approved wall and fence plan require the review and approval of Planning Division staff. The following shall apply:
- a. **Decorative Screen Walls.** Relocate the 14-foot high decorative screen walls 20 feet from the front property line, along Patterson Avenue. The screen wall shall include decorative pilasters with a cap at every 100 linear feet, subject to the review and approval of the Planning Division. The 14-foot-high screen wall on the east side of the site shall also consist of decorative materials and include decorative pilasters with a cap at every 100 linear feet.
 - b. **Wrought Iron Gates.** All tubular steel gates in public view shall be a minimum of eight (8) feet in height and be screened by a high-quality view-obscuring material, subject to Planning review and approval.
 - c. **Tubular Fence.** The proposed eight (8) foot high tubular steel fence shall be extended from where the retaining wall ends along the north property line to 10 feet from the front property line along Patterson Avenue, outside the front yard setback area.
 - d. **Graffiti.** All block/tilt-up walls shall be treated with a graffiti-resistant coat.
 - e. **Knox boxes** are required for all gates and shall be approved by the Fire Marshal and issued by the Building Division.
- 53 **Site Lighting Plan.** A site lighting plan that complies with the City's Outdoor Lighting Regulations and Mount Palomar Observatory's Dark Sky Ordinance shall be approved. The lighting plan shall include photometric, fixture details, and standard light elevations to meet 2700 KV illumination or less (to provide adequate illumination). High-efficiency fixtures with full-cut-off shields shall be used to prevent light and glare above the horizontal plane of the bottom of the lighting fixture. At least one foot-candle of light shall be provided in all parking lots and pedestrian areas for safety and security. All lighting shall be shielded downward to prevent light pollution from spilling onto adjacent parcels or the public right of way.
- 54 **Construction Plans.** All Planning Division and Engineering Department Conditions of Approval, proposed employee amenities, and the Mitigation Monitoring and Reporting Program shall be reproduced in full on construction drawings and grading plans immediately following the cover sheet of such plans. Each Condition shall be annotated on the construction plans for ease of reference (i.e., sheet and detail numbers).
- 55 **Fees.** The developer shall pay the following fees before the issuance of building permits:
- a. Stephen's Kangaroo Rat Mitigation Fees of \$500.00 per acre
 - b. Multiple Species Habitat Conservation Plan fees currently in effect
 - c. Current statutory school fees to all appropriate school districts
 - d. Any outstanding liens and development processing fees owed to the City
 - e. Appropriate Road and Bridge Benefit District fees
 - f. Appropriate City Development Impact Fees in effect at the time of development.

PRIOR TO THE ISSUANCE OF OCCUPANCY PERMITS:

56 **City Assessment and Community Facilities Districts.** The project shall be annexed into any assessment, community facilities, or similar district that provides funding for maintenance, services, or public improvements that benefit the project. The costs and benefits shall be described in the applicable district and annexation documents. The developer shall complete all actions required to complete such annexation before issuing a Certificate of Occupancy. This condition shall apply only to districts existing when the project is approved (or all requirements have been met for a certificate of occupancy, as applicable). Such districts may include but are not limited to the following:

- a. Landscape Maintenance District No. 1;
- b. Flood Control Maintenance District No. 1;
- c. Maintenance District No. 84-1;
- d. North Perris Community Facilities Assessment District; and
- e. Any other applicable City Assessment and Community Facilities Districts

57 **Truck Routes.** The applicant shall notify all truck drivers of the truck routes adopted by the City Council. Signs shall be provided on-site and within the public right-of-way to direct all trucks to use designated truck routes only as approved by the Engineering and Planning Departments.

Trucks shall access the I-215 Freeway by exiting the project site via Patterson to Harley Knox Boulevard, consistent with the City's adopted truck route.

Final Inspection. The applicant shall obtain occupancy clearance from the Planning Division by scheduling a final Planning inspection after final signoffs from the Building Division and Engineering Department. Planning Staff shall verify that all pertinent conditions of approval have been met. The applicant shall have all the required paving, parking, walls, site lighting, landscaping, and automatic irrigation installed and in good condition.

58 **Outstanding Fees.** Any processing fees due to the Planning Division shall be paid before building occupancy.

59 **On-Site Landscape Inspections.** The project applicant shall inform the on-site project manager and the landscape contractor of their responsibility to call for a final landscape inspection after the installation of all landscaping and irrigation systems is completely operational. Before calling for a final inspection, the City's "Certificate of Compliance" form shall be completed and signed by the designer/auditor responsible for the project and submitted to the project planner. The project planner shall sign off the "Certificate of Compliance" to signify code compliance and acceptance.

60 **Occupancy Clearance.** The applicant shall have all required paving, parking, screen walls, colors, and materials (per approved elevation plans), site lighting, landscaping, and automatic irrigation installed and in good condition prior to Planning sign-off.

END OF CONDITIONS



CITY OF PERRIS

STUART E. MCKIBBIN, CONTRACT CITY ENGINEER

CONDITIONS OF APPROVAL

P8-1462
March 13, 2023
TPM 38259 - DPR 21-00005
Prologis
Nance St. & Patterson Av.

With respect to the Conditions of Approval for the above referenced project, the City of Perris requires that the developer provide the following street improvements and/or road dedications in accordance with the City of Perris Municipal Code Title 18. It is understood that the site plan correctly shows all existing and proposed easements, traveled ways, rights-of-way, and drainage courses with appropriate Q's and that their omission may require resubmittal for further consideration. These Ordinances and the following conditions are essential parts and requirements occurring in one is as binding as though occurring in all. They are intended to be complimentary and to describe the conditions for a complete design of the improvements. Unless otherwise noted, all offsite improvements as conditions shall be installed prior to issuance of any occupancy permits. All questions regarding the true meaning of the conditions shall be referred to the City Engineer's office.

In the event of a conflict between any conditions stated below, those imposed by Planning Department and others, and requirements identified in the approved Traffic Impact Analysis, the most stringent in the opinion of the City shall prevail.

General Conditions:

1. The project grading shall be in a manner to perpetuate existing natural drainage patterns. Any deviation from this, concentration or increase in runoff must have approval of adjacent property owners and City Engineer. The developer/property owner shall accept the offsite runoff and convey to acceptable outlet.

2. Prior to commencement of any construction or installation of fencing in public right-of-way, an encroachment permit shall be obtained from the City Engineer's office.

3. Site circulation shall be such that auto and truck access, circulation and parking are distinct and separate.

4. Truck access to the site shall be limited to I-215/Harley Knox Boulevard Interchange, Harley Knox Boulevard and Patterson Avenue.

Truck access to and from Ramona Expressway and Perris Boulevard is prohibited.

Prior to Recordation of the Parcel Map:

5. The developer/property owner shall have approved improvement plans, executed subdivision agreement and posted securities.

6. The developer/property owner shall comply with the terms and conditions of the drainage requirements and construction of the drainage improvements identified in Condition no. 19 and post the respective bonds and securities as specified.

7. The developer/property owner shall submit the following to the City Engineer and Riverside County Flood Control and Water Conservation District (RCFCD) for review and approval:

- a. Onsite Precise Grading Plan and Erosion Control Plans; plans shall show the WDID No.
- b. Street Improvement Plans
- c. Storm Drain improvement Plans
- d. Signing and Striping Plans
- e. Water and Sewer Improvement Plans
- f. Street Light Plans prepared by a registered Electrical Engineer per City of Perris Safety Lighting Standards
- g. Geotechnical Report
- h. Hydrology and Hydraulic Report
- i. Final WQMP (for reference)

The design shall be in conformance with Eastern Municipal Water District (EMWD), RCFCD, Riverside County Transportation Department, Caltrans, City of Perris and ADA most recent standards, criteria and requirements and in effect at the time of construction and shall be coordinated with the approved plans of the adjacent developments.

8. Patterson Avenue is classified as a Collector (66'/44') per the General Plan. Adequate right-of-way shall be dedicated on Patterson Avenue

along the property frontage to accommodate a 33 foot half width dedicated right-of-way.

9. Nevada Avenue is classified as a Collector (66'/44'). Adequate right-of-way shall be dedicated on Nevada Avenue along the property frontage to accommodate a 33 foot half width dedicated right-of-way.

10. Nance Street is classified as a local (60'/40'). Adequate right-of-way shall be dedicated on Nance Street along the property frontage to accommodate a knuckle per County of Riverside Standard No. 801.

11. Nance Street from Patterson Avenue to the knuckle at Nance Street and Nevada Avenue, within the project site, shall be vacated; any and all underlying easement(s) shall be rescinded and any and all utilities and facilities removed as approved by the City Engineer.

12. Property line corner cutbacks shall be dedicated per County of Riverside Standard No. 805.

13. All rights-of-way and easements shall be offered for dedication to the public or other appropriate agencies and shall continue in force until the City or the appropriate agency accepts or abandons such offers. All dedications shall be free from all encumbrances as approved by the City Engineer.

14. Relinquish and waive rights of access to and from Patterson Avenue and Nevada Avenue on the Map other than the access opening as shown on the site plan.

15. In the event that offsite property is required to complete the required improvements, the developer/property owner shall make a good faith effort to acquire required offsite property interests, and if he or she should fail to do so, the developer/property owner shall, prior to submittal of the Final Map for recordation, enter into an agreement to complete the improvements. The agreement shall provide for payment by the developer/property owner of all costs incurred by the City to acquire the offsite property interests required in connection with the subdivision. Security of a portion of these costs shall be in the form of a cash deposit in the amount given in an appraisal report obtained by the developer/property owner (at developer/property owner cost). The appraiser shall be approved by the City prior to commencement of the appraisal.

16. The following statement shall be added to the Map:

"Notice of drainage fees" Notice is hereby given that this property is located in the Perris Valley Area Drainage Plan which was adopted by the City of Perris pursuant to Ordinance and Section 66483, et seq, of the

Government Code and that said property is subject to fees for said drainage area. Notice is further given that, pursuant to Ordinance 13-01, payment of the drainage fees shall be paid to the City of Perris prior to issuance of the building permit for the map, and that the property owner prior to issuance of the building permit, shall pay the fee required at the rate in effect at the time of issuance of the actual permit.

17. The developer/property owner shall sign the consent and waiver form to join the City's Lighting and Landscape Districts and City's Flood Control District as appropriate. The proposed streetlights and traffic signals shall be maintained by the City and cost paid by the developer/property owner through the said annexation.

Prior to Issuance of Grading Permit:

18. The developer/property owner shall submit the following to the City Engineer and Riverside County Flood Control and Water Conservation District (RCFCD) for review and approval:

- a. Onsite Precise Grading Plan and Erosion Control Plans; plans shall show the WDID No.
- b. Street Improvement Plans
- c. Storm Drain Improvement Plans
- d. Signing and Striping Plans
- e. Street Light Plans prepared by a registered Electrical Engineer per City of Perris Safety Lighting Standards
- f. Geotechnical Report
- g. Hydrology and Hydraulic Report
- h. Final WQMP (for reference)

The design shall be in conformance with Eastern Municipal Water District (EMWD), RCFCD, Riverside County Transportation Department, Caltrans, City of Perris and ADA most recent standards, criteria and requirements and in effect at the time of construction and shall be coordinated with the approved plans of the adjacent developments.

19. The developer/property owner shall comply with the drainage requirements and construction of the drainage improvements as specified below:

The ultimate drainage plan for this part of the City is dependent on the RCFCD construction of Perris Valley Master Drainage Plan Facility Lateral B Stage 4 along the March Air Reserve Base's boundary from Perris' north City limit to Heacock Street. The construction of Lateral B Stage 4 would serve as an adequate outlet for all runoff generated north of Harley Knox Boulevard. And the redirection of those flows to Lateral B Stage 4 would free up capacity in an existing Caltrans Reinforced Concrete Box (RCB) that runs in Harley Knox Boulevard. The Caltrans

RCB in Harley Knox Boulevard could then accept local flows from the area south of Harley Knox Boulevard, including onsite flows from this development.

Currently RCFCD is schedule to advertise Lateral B Stage 4 for bid in May 2023. Due to the timing of RCFCD's drainage improvements the drainage for this development may be constructed in phases.

The developer/property owner shall construct Perris Valley Master Drainage Plan Facility Line B-6 along the property's frontage on Patterson Avenue to collect the 10-year offsite storm runoff and convey them to the existing Caltrans RCB located at the intersection of Harley Knox Boulevard and Patterson Avenue. The developer/property owner shall also construct Perris Master Drainage Plan Facility Line B-6.1 from the site's northeast corner to convey 10-year onsite storm runoff to the existing Caltrans RCB located at the intersection of Harley Knox Boulevard and Nevada Avenue. Plans for these facilities must be approved and bonded for prior to the issuance of Building Permits. Temporary Occupancy Permits shall not be issued until Line B-6 and Line B-6.1 are completed.

The request for Building Permits vs. Grading Permit is because RCFCD does not want to issue their encroachment permit until Lateral B Stage 4 and Line B-8 are completely constructed. In the event that Lateral B Stage 4 is not under construction, City may consider issuing the Building Permits and Temporary Occupancy Permit, however no Final Certificate of Occupancy will be issued.

The developer/property owner shall construct Line B-8 to connect the existing Caltrans RCB directly to Lateral B Stage 4. Line B-8 is located about 1260-feet north of Harley Knox and will run east from Patterson Avenue and discharge flows into Lateral B Stage 4 after it is constructed by RCFCD. The plans for Line B-8 shall be in plan check with RCFCD, the right-of-way across APN 294-220-010 shall be acquired, and bonds posted, prior to the issuance of Building Permits. Line B-8 shall be maintained by RCFCD and the developer/property owner shall enter into a tri-party cooperative agreement with RCFCD and the City covering the terms of plan check, right-of-way transfer, inspection, operation, and maintenance, prior to issuance of Final Certificate of Occupancy.

Final Certificate of Occupancy shall not be issued until Line B-8 is completed to the satisfaction of the City Engineer.

Provision of Master Drainage Plan facilities and any connection to Master Drainage Plan facilities will require an encroachment permit from RCFCD.

20. The most northerly driveway on Patterson Avenue shall be designated for truck access only and shall be limited to left-in/right-out only.
21. The driveway on Patterson Avenue aligned with California Avenue (to the west of Patterson Avenue) shall be designated for auto access only.
22. The driveway on Patterson Avenue aligned with Nance Street (to the west of Patterson Avenue) shall be designated for truck access only and shall be limited to left-in/right-out only.
23. The most southerly driveway on Patterson Avenue shall be designated for auto access only.
24. The driveway on Nance Street shall be designated for emergency access only.
25. The driveways shall be per County of Riverside Standard No. 207A and shall include wet set concrete truncated domes in compliance to ADA standards and requirements.
26. The developer/property owner shall pay to the City \$500,000 for their contribution towards I-215/Ramona Expressway Interchange and I-215/Harley Knox Boulevard Interchange and other improvements. This one-time contribution is above and beyond DIF, TUMF, RBBB and other City fees, and is not reimbursable.

Prior to Issuance of Building Permit:

27. The developer/property owner shall comply with the terms and conditions of the drainage requirements and completing the construction of the drainage improvements as identified in Condition no. 19.
28. The project site is located within the limits of Perris Valley Area Drainage Plan (ADP) for which drainage fees have been adopted by City. Drainage fees shall be set forth under the provisions of the "Rules and Regulations of Administration of Area Drainage Plan". Acreage for the project site's impervious area shall be provided.

The developer/property will be eligible for ADP fee credit in exchange for the construction of Line B-8 since this system is a benefit to the City.

29. Water and sewer Improvement Plans, per Fire Department and Eastern Municipal Water District (EMWD) standards, shall be submitted to the City Engineer for review and approval.
30. Fire Department and EMWD approvals of the Water Improvement Plans are required prior to City Engineer's approval.

31. Paved access shall be provided to the proposed buildings per the Precise Grading Plans.

32. The developer/property owner shall submit a compaction certification from the Soils Engineer in compliance with the approved geotechnical/soils report.

Prior to Issuance of Certificate of Occupancy:

33. The developer/property owner shall comply with the terms and conditions of the drainage requirements and completing the construction of the drainage improvements as identified in Condition no. 19.

34. Patterson Avenue (Collector - 66'/44') along the property frontage within the dedicated right-of-way shall be improved to provide for a 44 foot wide asphalt pavement (using a TI of 9.0 and PG 70-10), 6 inch curb and gutter 22 feet east of centerline, a 6 foot wide sidewalk, Class II bike lane per the Active Transportation Plan and streetlights subject to the photometric analysis, per City of Perris, County of Riverside and Caltrans standards.

35. Patterson Avenue (Collector - 66'/44') from northerly project boundary to Harley Knox Boulevard within the dedicated right-of-way shall be improved to provide for asphalt pavement transition lanes per Caltrans standards, the widths and lengths of the lanes shall be determined by the project's Traffic Engineer as approved by City Engineer.

36. The existing power poles on Patterson Avenue along the property frontage shall be removed and cables (under 66 kv) including the communication cables shall be undergrounded. The developer/property owner shall provide an undergrounding of utilities study prepared by a utility consultant/electrical engineer analyzing and determining the extent of conformance.

37. Nevada Avenue (Local - 66'/44') along the property frontage within the dedicated right-of-way shall be improved to provide for a 37 foot wide asphalt pavement (using a TI of 7.0 and PG 70-10), 6 inch curb and gutter 22 feet west of centerline, a 6 foot wide sidewalk and streetlights subject to the photometric analysis, per City of Perris, County of Riverside and Caltrans standards.

38. Nevada Avenue (Local - 60'/40') from northerly project boundary to Harley Knox Boulevard shall be improved to provide for a 30 foot wide asphalt pavement (using a TI of 7.0 and PG 70-10) per City of Perris, County of Riverside and Caltrans standards.

39. The existing power poles on Nevada Avenue along the property frontage shall be removed and relocated as applicable and cables (under 66 kv) including the communication cables shall be undergrounded. The developer/property owner shall provide an undergrounding of utilities study prepared by a utility consultant/electrical engineer analyzing and determining the extent of conformance.

40. The knuckle at Nance Street and Nevada Avenue at project boundary, shall be improved per County of Riverside Standard No. 801 to provide for asphalt pavement (using a TI of 7.0 and PG 70-10), including 6 inch curb and gutter, a 6 foot wide sidewalk and streetlights subject to the photometric analysis, per City of Perris, County of Riverside and Caltrans standards.

41. Nance Street (Local - 60'/40') from the knuckle at the project boundary to Webster Avenue shall be improved to provide for a 30 foot wide asphalt pavement (using a TI of 7.0 and PG 70-10), including transition lanes, per City of Perris, County of Riverside and Caltrans standards.

42. The conditions of the existing pavement on Patterson Avenue along the property frontage and the extensions shall be evaluated by the developer/property owner in order for the City Engineer to determine the extent of pavement rehabilitation. If the existing pavement is in good condition, the developer/property owner may use grind and overlay technique as determined by the City Engineer.

43. The developer/property owner shall provide for utility trench surface repair as directed by the City Engineer.

44. Associated existing signing and striping shall be refreshed and any appurtenances damaged or broken during the development of this project shall be repaired or removed and replaced by the developer/property owner to the satisfaction of the City Engineer. Any survey monuments damaged or destroyed shall be reset by qualified professional pursuant to the California Business and Professional Code 8771.



CITY OF PERRIS

PUBLIC WORKS DEPARTMENT

Weed Abatement

NPDES Services

Flood Control and Landscape Districts

MEMORANDUM

Date: December 05, 2022

To: Mary Blais, Planner

From: Michael Morales, CIP Manager

By: Chris Baldino, Landscape Inspector **CB**

Subject: DPR 21-00005– Conditions of Approval

Proposal to construct a 579,986 square foot Industrial building on East Patterson Ave and Nevada Ave. within the Perris Valley Commerce Center Specific Plan.

-
1. **Dedication and/or Landscape Maintenance Easement.** Offer of Dedication and Landscape Maintenance Easement for City landscape maintenance district shall be provided as follows:
 - **Patterson Ave.** - Provide offer of dedication as needed to provide for full half width Street (66' ROW (33' half width), curb gutter, sidewalk, and off-site landscaping requirements, per City General Plan, including minimum 11' public parkway from back of curb.
 - **Nevada Ave.** - Provide offer of dedication as needed to provide for full half width Street (66' ROW (33' half width), curb gutter, sidewalk, and off-site landscaping requirements, per City General Plan, including minimum 11' public parkway from back of curb.
 2. **Landscape Maintenance Easement and Landscape Easement Agreement.** The developer shall provide, for review and approval, an Offer of Dedication and certificate of acceptance, complete with legal plat map and legal description to the City of Perris. In addition, if required by the City of Perris, the Developer shall provide an additional landscape easement and Landscape easement agreement, acceptable to the City of Perris. The City shall record the same with the Riverside County Recorder's Office, and the recorded instrument shall be returned to the City Clerk of the City of Perris for filing.
 3. **Landscaping Plans.** Three (3) copies of Construction Landscaping and Irrigation Plans for the off-site landscaping, including any medians or other landscape areas along the dedications shall be submitted to the Planning Department for approval and shall be accompanied by the appropriate filing fee. The landscape and irrigation plan shall be prepared by a registered landscape architect and conform to the requirements of Chapter 19.70 of the Municipal Code. The location, number, genus, species, and container size of the plants shall be shown. This landscape plan shall be titled "Off-site Landscape Plan for DPR 21-00005" and shall be exclusive of any private property, on-site landscaping. Elements of the Landscape Plan shall include but not be limited to:
 - a. **Landscape Limits** – Limits of right-of-way areas or easement areas, defined by concrete mow curb, fully dimensioned, that are to be annexed into the Landscape Maintenance District. A planting palette and

hardscape plan intended to meet the design intent of the Landscape Guidelines in effect for the area; or if no such guidelines exist the design intent of neighboring development, as determined by the Engineering Administration and Special Districts Division, including:

- **Patterson Ave** – Per Section 6.0-21 Streetscape Landscape design guidelines and planting pallet for Collector and figure 6.0-9, of the PVCCSP for sizing and spacing requirements. Street tree: *Platanus x acerfolia* 'London Plane Tree. Use of drought resistant shrubs and groundcover intended to complement the existing parkway along Patterson Ave. including but not limited to the following: *Callistemon* 'Little John', *Hesperaloe parviflora* 'Red Yucca', *Lantana M.* 'Gold Rush Lantana', *Myoporum parviflora*.
 - **Naveda Ave.** – This parkway will be a non-irrigated parkway with a design of 4" to 6" Arizona grouted cobble in a half moon design. Within the half moon areas without cobble artificial turf or a different colored grouted cobble would be required.
 - **Nance Street** – At the knuckle of Nance Street there is a small section of right-of-way to be concrete instead of landscape.
- b. **Irrigation** – A list of irrigation system components intended to meet the performance, durability, water efficiency, and anti-theft requirements for Special District landscape areas as determined by the Engineering Administration and Special Districts Division. Components shall include, but not be limited to Salco or equal on flexible PVC risers, Sentry Guard Cable Guard and Union Guard, and backflow Wilkens Model 375 (or equal). Controller shall include an ET based controller with weather station that is centrally controlled capable and wi-fi ready (WeatherTrak ET Pro3 Smart Controller, or equal, with Rain Sensor). At the discretion of the Engineering Administration and Special Districts Division public landscape areas utilizing no more than 6 valves/stations, programmed to irrigate consecutively, and none simultaneously, may propose the use of an alternative ET based controller with weather station that is centrally controlled capable and wi-fi ready, such as the Weathermatic System or equal. Proposed system shall be complete with wireless weather station, aircard with flow, one year bundle service, blade antenna and flow sensor.
- c. **Benefit Zone Quantities** – Include a Benefit Zone quantities table (i.e. SF of planting areas, turf, number of trees, SF. of hardscape, etc.) in the lower right hand corner of the cover sheet for off-site landscape areas, indicating the amount of landscaping the district will be required to maintain.
- d. **Meters** – Each District is required to be metered separately. All electrical and water meters shall be located in locations that are easily accessible to maintenance staff while not visually obtrusive in the street scene and away from street intersections. Show location of separate water and electrical utility meters intended to serve maintenance district areas exclusively. Show locations of water and electrical meter for landscape district. Show location of water and electrical meter for flood control district. Show location of electrical meter for Traffic signal and street lighting district, on respective plans. Coordinate location of meters on landscape and civil engineering plan.
- e. **Controllers** - The off-site irrigation controllers are to be located within the right of way (preferably within the off-site landscape area). All point of connection equipment including irrigation controller pedestals, electrical meter pedestals, and backflow preventers are to be located in locations that are easily accessible to maintenance staff while not visually obtrusive in the street scene, and away from street intersections. Backflow preventers are to be screened on at least three sides with (5) gallon plant material. The fourth side shall be open to the back of the landscape area in order to allow the backflow cage to be opened

without interference with plant materials. Backflow cages shall meet the required City of Perris Engineering Standards in effect at the time of approval.

- f. **Recycled Water** - If applicable. The project landscape architect shall coordinate with EMWD to verify if the site will be served with recycled water and design all irrigation and landscape plans to meet the requirements of EMWD and provide additional irrigation components as needed.
 - g. **EMWD Landscape Plan Approval** – The project landscape architect shall submit a copy of all irrigation plans and specifications to EMWD for approval. The project landscape architect must confirm with EMWD that the plans have been approved by EMWD and submit written proof of approval by EMWD prior to the City approving the final Landscape Plans. Until the final landscape plan has been approved by the City of Perris, the maintenance areas depicted cannot be accepted by the City for maintenance. The developer shall coordinate both reviews to ensure acceptability of plans by both EMWD and the City of Perris, prior to approval by either agency.
 - h. **Landscape Weed Barrier** - Weed cloth with a minimum expected life of 10-years shall be required under all gravel, rock, or cobble areas.
 - i. **Wire Mesh and Gravel at Pull Boxes**- Provide wire mesh and gravel layer within valve boxes to prevent rodent intrusion.
 - j. **Concrete Maintenance Band at Medians and Mortar Cobble turn Land** – Provide 12" wide concrete maintenance band (safety edge) around entire median. At turn pockets provide mortared cobble creek bed, round stone sized 6" to 12".
 - k. **Perimeter Walls Graffiti Coating** – Provide anti-graffiti coating at all perimeter walls. Acceptable products shall include Vitrocem Anti-Graffiti Coating or equal.
4. **Landscape Inspections.** The project applicant shall inform the on-site project manager and the landscape contractor of their responsibility to call for only "OFF-SITE" landscape and irrigation inspections at the appropriate stages of construction. Inspections shall be scheduled at least two-working days (Monday through Friday) prior to actual inspection. Contact Public Works-Engineering Administration/Special Districts at (951) 657-3280 to schedule inspections.
- **Inspection #1** - Trenches open, irrigation installed, and system pressurized to 150 PSI for four hours.
 - **Inspection #2** - Soil prepared, and plant materials positioned and ready to plant.
 - **Inspection #3** - Landscaping installed, irrigation system fully operational, and request for "Start of 1 year Maintenance Period" submitted, with all required turn-over submittal items provided to Public-Works Engineering Administration/Special Districts.
 - **Turn-Over Inspection**– On or about the one-year anniversary of Inspection #3, Developer shall call for an inspection to allow the City to review and identify any potential irrigation system defects, dead plants, weed, debris or graffiti; stressed, diseased, or dead trees; mulch condition, hardscape or other concerns with the landscape installation; or to accept final turn over of the landscape installation. At his sole expense, the Developer shall be responsible for rectifying system and installation deficiencies, and the one-year maintenance period shall be extended by the City until all deficiencies are cured to the satisfaction of the City. If in the opinion of the City's Landscape Inspector the landscape installation is

in substantial compliance with the approved landscaping plans, the irrigation and communication system is functioning as intended, and the landscape installation is found to be acceptable to the City, then the Inspector shall recommend to the City's Special District Coordinator to accept turn-over of water and electrical accounts, wi-fi communication contracts and the entire landscape installation.

5. **One Year Maintenance and Plant Establishment Period**-The applicant will be required to provide a minimum of a one (1) year maintenance and plant establishment period, paid at the sole expense of applicant. This one-year maintenance period commences upon the successful completion of Inspection #3 discussed above, and final approval by the City. During this one-year period the applicant shall be required to maintain all landscape areas free of weeds, debris, trash, and graffiti; and keep all plants, trees, and shrubs in a viable growth condition. Prior to the start of the one-year maintenance period, the Developer shall submit a weekly Landscape Maintenance Schedule for the review and approval by the City's Special Districts Division. City shall perform periodic site inspections during the one-year maintenance period. The purpose of these periodic inspections is to identify any and all items needing correction prior to acceptance by the City at the conclusion of the one-year maintenance period. Said items needing correction may include but are not limited to: replacement of dead or diseased plant materials, weeding, replenishment of mulches, repair of damaged or non-functioning irrigation components, test of irrigation controller communications, etc. During this period, the City shall begin the annual assessment of the benefit zone in preparation for the landscape installation turn-over to City maintenance staff.
6. **Street/Off-Site Improvements.** The applicant shall submit street improvement plans, accompanied by the appropriate filing fee to the City Engineering Department. Details of treatments off-site improvements, including lighting shall meet both the City Engineer's Design Guidelines, and the additional requirements of the Engineering and Special Districts Division. Components shall include, but not be limited to:
 - a. **Street Lighting**-If Street lighting is required, lighting shall meet the type, style, color and durability requirements, necessary for energy efficiency goals, maintenance and longevity of improvements of the City Engineer's Office. As determined by the City, new streetlights may be required to be deeded to City of Perris, and not SCE. Streetlights deeded to City of Perris shall be constructed per LS-3 account billing standard, which shall include an individually metered pedestal for streetlights.
 - b. **Acceptance By Public Works/Special Districts**- Lighting District facilities required by the City Engineer's Office shall be installed and fully operational and approved by final inspection by the City Engineer's Office, and the City's Consulting Traffic Signal Inspection Team (Riverside County TLMA) at (951) 955-6815. Prior to acceptance for maintenance of "Off-site" traffic signal and lighting facilities by the Public Works-Engineering and Administration Division/Special Districts, the developer shall contact the Public Works Special Districts Division at (951) 657-3280 to schedule the delivery of all required turn-over submittal items. Prior to acceptance into Lighting District 84-1, coordinate turn-over information pertaining to Street Lights, and Traffic Signal Electrical/SCE Service Meters with Wildan Financial Services, the City's Special Districts Consulting Firm at (951) 587-3564. (i.e. Provide electrical meter number, photo of pedestal, and coordinate "request for transfer of billing information" with SCE and City for all new service meters). Developer shall pay 18-month energy charges to the City of Perris for all off-site street lighting. Call Wildan Financial Services, Inc. for amount due, and to obtain receipt for payment. Obtain and provide a clearance form from Riverside County TLMA indicating completion of all punch list items from traffic signal construction. Submit one large format photocopy of Traffic Signal as-built plans and timing sheets.
7. **Water Quality Management Plans.** The applicant shall submit a Preliminary and Final WQMP, accompanied

by the appropriate filing fee to the Planning Department and City Engineering Department, respectively. Details for treatment control facilities shall meet both the Riverside County WQMP Design Guidelines, and the additional requirements of the Engineering and Special Districts Division intended to reduce long term maintenance costs and longevity of improvements. Components shall include, but not be limited to:

- **Storm Drain Screens-**If off-site catch basins are required by the City Engineer's Office, connector pipe screens shall be included in new catch basins to reduce sediment and trash loading within storm pipe. Connector pipe screens shall meet the type, style, and durability requirements of the Public Works Engineering Administration and Special Districts Division.
- **WQMP Inspections-** The project applicant shall inform the on-site project manager and the water quality/utilities contractor of their responsibility to call for both "ON-SITE" and OFF-SITE" WQMP Inspections at the appropriate stages of construction. Contact CGRM at (909) 455-8520 to schedule inspections.
- **Acceptance By Public Works/Special Districts-**Both on-site and off-site flood control/water quality facilities required for the project, as depicted in the Final WQMP, shall be installed and fully operational, and approved by final inspection by the City's WQMP Consultant, CGRM. The Developer shall obtain a final Clearance Letter from CGRM indicating compliance with all applicable Conditions of Approval for the approved WQMP. The developer shall deliver the same to the Public Works-Engineering and Administration Division/Special Districts. In addition, prior to acceptance by the City, the developer shall submit a Covenant and Agreement describing on-going maintenance responsibilities for on-site facilities per the approved WQMP, to the Public Works Engineering Administration and Special Districts Division. The Public Works Engineering Administration and Special Districts Division will review and approve the Covenant and Agreement. The City shall record the same with the Riverside County Recorder's Office, and the recorded instrument shall be returned to the City Clerk of the City of Perris for filing.

8. **Flood Control District #1 Maintenance Acceptance.** Flood Control District facilities required by the City Engineer's Office shall be installed and fully operational, and approved by final inspection by the City Engineer's Office. Prior to acceptance for maintenance of "Off-site" flood control facilities by the Public Works-Engineering and Administration Division/Special Districts the developer shall contact the Public Works Special Districts Division at (951) 657-3280 to schedule the delivery of all required turn-over submittal items including as-built storm drain plans in electronic PDF format, one large format photo-copy of as-built plans, storm drain video report in electronic format, and hardcopy of video report with industry standard notations and still photos made during video runs (i.e. facilities sizes, off-sets or damage, facility type, dirt and debris, etc.). The flood control facilities shall be turned over in a condition acceptable to the City, and the developer shall make all necessary repairs and perform initial maintenance to the satisfaction of the City.
9. **Assessment Districts.** Prior to permit issuance, developer shall deposit \$5,250 per district, \$15,750 total due. Payment is to be made to the City of Perris, and the check delivered to the City Engineer's Office. Payment shall be accompanied by the appropriate document for each district indicating intent and understanding of annexation, to be notarized by property owner(s):
 - **Consent and Waiver for Maintenance District No. 84-1** - New street lighting proposed by the project, as determined by the City Engineer
 - **Consent and Waiver for Landscape Maintenance District No. 1** – New off-site parkway landscape proposed by the project on Patterson Ave, and Nevada Ave.

- ***Petition for Flood Control Maintenance District No. 1*** -For Off-site Flood Control Facilities proposed by the project, as determined by the City Engineer.

- Original notarized document(s) to be sent to:
Daniel Louie
Wildan Financial Services
27368 Via Industria, #200
Temecula, CA 92590

- a. Prior to final map recordation or final certificate of occupancy the developer shall annex into the aforementioned districts, posting an adequate maintenance performance bond to be retained by the City as required by the City Engineer. Upon receipt of deposit and Consent and Waiver Forms, the developer shall work with City to meet all required milestones for annexations.
 - i. City prepares the Engineer's Reports which includes a description of the improvements to be maintained, an annual cost estimate and annual assessment amounts.
 - ii. Reports are reviewed and approved by the property owner. The assessment ballots will be based on these Reports.
 - iii. The Reports and corresponding resolutions are placed, for approval, on the City Council Meeting Agenda. City Council action will include ordering the assessment ballots and setting a Public Hearing for no sooner than 45 days. Property owner attendance at this City Council Meeting is not required.
 - iv. The assessment ballots are sent to the property owner and are opened by the City Clerk at the close of the Public Hearing. With a "YES" vote by the property owner the City Council can move forward with the Resolution that Confirms the Annexation. Property owner attendance at this Public Hearing is not required.
 - v. Confirmation by the City Council completes the annexation process and the condition of approval has been met.



Dennis Grubb and Associates, LLC

Assisting Cities Build Safe Communities

Fire Department Development Review Comments

December 28, 2022

City of Perris
Attn: Alfredo Garcia
135 N. D Street
Perris, CA 92570-2200

Subject: Development Plan Review for DPR21-00005

As requested, a review of the subject property was completed. The Following conditions shall apply to the project:

1. The project shall comply with all requirements set forth by the California Code of Regulations Title 24 Parts 1-12 respectively.
2. The adopted edition of the California Code of Regulations, Title 24, Parts 1 through 12, and the Perris Municipal Code shall apply at the time the architectural plans are submitted for construction permits.
3. Prior to the to the issuance of a grading permits, evidence of sufficient fire flow of 4,000 GPM for 4- hours shall be provided to the City of Perris. The City of Perris Building and Fire Marshal Water Available/Fire Flow Form shall be utilized.
4. A fire department access road complying with the CFC, Chapter 5 and the approved fire department access plans shall be installed prior to building construction.
5. All required fire hydrants shall be installed and operational prior to building construction. All fire hydrants shall remain operational during construction.
6. All required fire hydrants shall be readily visible and immediately accessible. A clear space of not less than 3-feet shall be maintained at all times.
7. The private underground fire-line system shall be a looped design.

8. The private underground fire-line system shall have indicating sectional valves for every five (5) appurtenances.
9. A minimum of two points of connection to the public water shall be provided for the private fire-line water.
10. The Fire Department Connection (FDC) shall be located within 100 feet of a public fire hydrant. The fire hydrant shall be on the same side of the street. A vehicle access roadway/approach shall not be placed between the FDC and fire hydrant.
11. Prior to construction a temporary address sign shall be posted and clearly visible from the street.
12. The permanent building address shall be provided and either internally or externally lighted during hours of darkness. The address shall be clearly visible from the street fronting the property and comply with California Fire Code Section 505.1 for size and color.
13. City of Perris approval shall be obtained prior to the storage and/or use of hazardous materials as defined by the California Fire Code.
14. The building shall be provided with an automatic fire sprinkler system in accordance with NFPA 13. Construction plans shall be submitted for review and approval to the City of Perris prior to installation.
15. Prior to building final, the building shall be provided with a Knox Lock key box located no more than seven-feet above the finished surfaced and near the main entrance door.
16. Prior to building final the building shall be provided with an emergency radio communication enhancement system. The emergency radio communication enhancement system shall meet the requirements of CFC § 510 and all applicable subsection. The system shall be installed and inspected by the City of Perris Building Department before the Certificate of Occupancy is issued. The requirement can be waived by the Fire Marshal if the building is evaluated by an Emergency Radio Communication Specialist license by FCC, who certifies the building meets the emergency communications capability as specified by the California Fire Code § 510. The certification shall be in the form of a written report which outlines the analysis used in determining the building meets the emergency communications without an enhancement system.

Respectfully,



Dennis Grubb, CFPE



CITY OF PERRIS
COMMUNITY SERVICES

MEMO

Date: June 9, 2021
To: Alfredo Garcia, Project Planner
From: Sabrina Chavez, Director of Community Services
Cc: Arcenio Ramirez, Community Services Manager
Jessica Galloway, Project Coordinator
Joshua Estrada, Parks Coordinator
Subject: Development Plan Review 21-00005 – Comments

Community Services Staff reviewed DPR 21-00005 and offer the following comment(s):

Development Impact Fees

- The Project is subject to payment of Industrial Park Development Impact Fees.
- This Project is subject to payment of Public Art Development Impact Fees.

Special Districts

- The project shall annex into the Community Facilities District No. 2018-02 (Public Services)

Trails

Add Class II bike lane on Patterson Avenue as identified in the Active Transportation Plan 2020, refer to Engineering comments.

SRC COMMENTS
***** BUILDING & SAFETY *****

Planning Case File No(s): DEVELOPMENT PLAN REVIEW #21-00005

Case Planner: Alfredo Garcia (951) 943-5003,

Applicant: DJ Arellano

Location: East of Patterson Ave., and North of Nance Street

Project: Proposal to construct a 579,986 SF industrial building.

APN(s): 314-153-015 thru 314-153-042, 314-153-044, 314-153-046 and 314-153-048

Reviewed By: David J. Martinez, CBO

Date: 5-10-2021

BUILDING AND SAFETY CONDITIONS

1. Shall comply with the latest adopted State of California 2019 editions of the following codes as applicable:
 - A. 2019 California Building Code
 - B. 2019 California Electrical Code
 - C. 2019 California Mechanical Code
 - D. 2019 California Plumbing Code
 - E. 2019 California Energy Code.
 - F. 2019 California Fire Code
 - G. 2019 California Green Building Standards Code.
2. You will be required to provide proper fire access to the entire site.
3. The proposed site will have to comply with the new EV charging station regulations.
4. None of the proposed buildings can cross any property lines. A lot line adjustment may be required prior to the construction of the project.

PRIOR TO ISSUANCE OF BUILDING/CONSTRUCTION PERMITS

1. The following items shall be completed and/or submitted as applicable – prior to the issuance of building permits for this project:
 - A. Precise grading plans shall be approved

- B. Rough grading completed
- C. Compaction certification
- D. Pad elevation certification
- E. Rough grade inspection signed off

FIRE CONDITIONS: To Be provided by Dennis Grubb

ATTACHMENT 2

Mitigation Monitoring and Reporting Program

*Due to the size of the files, the documents
are available online at:*

[https://www.cityofperris.org/departments/
development-
services/planning/environmental-
documents-for-public-review/-folder-
333#docan1206 1313 479](https://www.cityofperris.org/departments/development-services/planning/environmental-documents-for-public-review/-folder-333#docan1206_1313_479)

EXHIBIT B

Location / Aerial Map

LOCATION / AERIAL VIEW



EXHIBIT C

Existing PVCCSP Specific Plan

Existing Land Use – PVCCSP
Light Industrial (LI) and General Industrial (GI)




EXHIBIT D

MARB/IPA ALUCP Map

MARP/IPA ALUCP Map




EXHIBIT E

Existing and Proposed Modifications to Applicable PVCCSP Figures



Figure 3.0-1, Circulation Plan





Figure 3.0-4, Mass Transit Routes



Q:\2017\17-5046\GIS\PVCC_SP_MassTransitRoutes.mxd, Map revised July 12, 2017.



Figure 3.0-5, Trails System






Figure 3.0-7. Existing EMWD Water





Figure 3.0-8. Existing EMWD Sewer







Figure 3.0-9. Existing EMWD Recycled Water



G:\01717-0046\GIS\PVCC_SP_ExtEMWDRecycled.mxd Map revised July 13, 2017



Figure 3.0-12, Existing Natural Gas






FIGURE 3.0-13, Existing Electric






Figure 3.0-14, Existing Telephone






Figure 3.0-15, Existing Cable TV




EXHIBIT F

Tentative Parcel Map TPM-38259

EXHIBIT G

Project Plans



PROLOGIS[®]

2100 PATTERSON AVENUE
PERRIS, CA 92571



PATTERSON & NANCE
PERRIS, CA


PROJECT
3RD PLANNING SUBMITTAL




HERDMAN
ARCHITECTURE + DESIGN
ACT 110881
04.26.2023
3D VIEW

A0


DATE PLOTTED: 04/26/2023 10:58:11 AM




1 ENLARGED TRASH ENCLOSURE PLAN
1/8" = 1'-0"



2 WEST S.E. ELEVATION
1/8" = 1'-0"



3 SOUTH S.E. ELEVATION
1/8" = 1'-0"




4 NORTH S.E. ELEVATION
1/8" = 1'-0"

REVISED TO SHOW REVISIONS TO ENLARGED ENCLOSURE


- 101 TRASH ENCLOSURE PLAN
- 102 WEST S.E. ELEVATION
- 103 SOUTH S.E. ELEVATION
- 104 NORTH S.E. ELEVATION
- 105 ENLARGED TRASH ENCLOSURE PLAN
- 106 WEST S.E. ELEVATION
- 107 SOUTH S.E. ELEVATION
- 108 NORTH S.E. ELEVATION

EXTERIOR WALL COLOR SCHEDULE & NOTES


1. EXTERIOR WALL
2. EXTERIOR WALL
3. EXTERIOR WALL
4. EXTERIOR WALL
5. EXTERIOR WALL
6. EXTERIOR WALL
7. EXTERIOR WALL
8. EXTERIOR WALL
9. EXTERIOR WALL
10. EXTERIOR WALL
11. EXTERIOR WALL
12. EXTERIOR WALL
13. EXTERIOR WALL
14. EXTERIOR WALL
15. EXTERIOR WALL
16. EXTERIOR WALL
17. EXTERIOR WALL
18. EXTERIOR WALL
19. EXTERIOR WALL
20. EXTERIOR WALL
21. EXTERIOR WALL
22. EXTERIOR WALL
23. EXTERIOR WALL
24. EXTERIOR WALL
25. EXTERIOR WALL
26. EXTERIOR WALL
27. EXTERIOR WALL
28. EXTERIOR WALL
29. EXTERIOR WALL
30. EXTERIOR WALL
31. EXTERIOR WALL
32. EXTERIOR WALL
33. EXTERIOR WALL
34. EXTERIOR WALL
35. EXTERIOR WALL
36. EXTERIOR WALL
37. EXTERIOR WALL
38. EXTERIOR WALL
39. EXTERIOR WALL
40. EXTERIOR WALL
41. EXTERIOR WALL
42. EXTERIOR WALL
43. EXTERIOR WALL
44. EXTERIOR WALL
45. EXTERIOR WALL
46. EXTERIOR WALL
47. EXTERIOR WALL
48. EXTERIOR WALL
49. EXTERIOR WALL
50. EXTERIOR WALL
51. EXTERIOR WALL
52. EXTERIOR WALL
53. EXTERIOR WALL
54. EXTERIOR WALL
55. EXTERIOR WALL
56. EXTERIOR WALL
57. EXTERIOR WALL
58. EXTERIOR WALL
59. EXTERIOR WALL
60. EXTERIOR WALL
61. EXTERIOR WALL
62. EXTERIOR WALL
63. EXTERIOR WALL
64. EXTERIOR WALL
65. EXTERIOR WALL
66. EXTERIOR WALL
67. EXTERIOR WALL
68. EXTERIOR WALL
69. EXTERIOR WALL
70. EXTERIOR WALL
71. EXTERIOR WALL
72. EXTERIOR WALL
73. EXTERIOR WALL
74. EXTERIOR WALL
75. EXTERIOR WALL
76. EXTERIOR WALL
77. EXTERIOR WALL
78. EXTERIOR WALL
79. EXTERIOR WALL
80. EXTERIOR WALL
81. EXTERIOR WALL
82. EXTERIOR WALL
83. EXTERIOR WALL
84. EXTERIOR WALL
85. EXTERIOR WALL
86. EXTERIOR WALL
87. EXTERIOR WALL
88. EXTERIOR WALL
89. EXTERIOR WALL
90. EXTERIOR WALL
91. EXTERIOR WALL
92. EXTERIOR WALL
93. EXTERIOR WALL
94. EXTERIOR WALL
95. EXTERIOR WALL
96. EXTERIOR WALL
97. EXTERIOR WALL
98. EXTERIOR WALL
99. EXTERIOR WALL
100. EXTERIOR WALL



2 LINE OF SIGHT FROM NANCE STREET
1/8" = 1'-0"



3 LINE OF SITE FROM PATTERSON AVENUE
1/8" = 1'-0"



1 WEST TRUCK YARD - NORTHWEST GATE ELEVATION
15'-0" x 1'-0"

2 WEST TRUCK YARD - NORTHWEST GATE ELEVATION
15'-0" x 1'-0"

3 WEST TRUCK YARD - SITE WALL ELEVATION
15'-0" x 1'-0"

4 WEST TRUCK YARD - SITE WALL ELEVATION
15'-0" x 1'-0"

5 WEST TRUCK YARD - SITE WALL ELEVATION
15'-0" x 1'-0"

6 WEST TRUCK YARD - SITE WALL ELEVATION
15'-0" x 1'-0"

7 WEST TRUCK YARD - SITE WALL ELEVATION
15'-0" x 1'-0"

8 WEST TRUCK YARD - SITE WALL ELEVATION
15'-0" x 1'-0"

9 WEST TRUCK YARD - SOUTH-WEST GATE ELEVATION
15'-0" x 1'-0"

10 TYPICAL PLASTER CAP PLAN
15'-0" x 1'-0"


REFERENCES

- 1. CITY OF PERRIS, CALIFORNIA. PERRIS TRUCK YARD. 2011.
- 2. CALIFORNIA STATE ARCHITECTURE BOARD. ARCHITECTURAL DRAWING STANDARDS. 2011.
- 3. AMERICAN INSTITUTE OF ARCHITECTS. ARCHITECTURAL DRAWING VocabularY. 2003.
- 4. CALIFORNIA STATE ARCHITECTURE BOARD. ARCHITECTURAL DRAWING STANDARDS. 2011.
- 5. CALIFORNIA STATE ARCHITECTURE BOARD. ARCHITECTURAL DRAWING STANDARDS. 2011.
- 6. CALIFORNIA STATE ARCHITECTURE BOARD. ARCHITECTURAL DRAWING STANDARDS. 2011.
- 7. CALIFORNIA STATE ARCHITECTURE BOARD. ARCHITECTURAL DRAWING STANDARDS. 2011.
- 8. CALIFORNIA STATE ARCHITECTURE BOARD. ARCHITECTURAL DRAWING STANDARDS. 2011.
- 9. CALIFORNIA STATE ARCHITECTURE BOARD. ARCHITECTURAL DRAWING STANDARDS. 2011.
- 10. CALIFORNIA STATE ARCHITECTURE BOARD. ARCHITECTURAL DRAWING STANDARDS. 2011.
- 11. CALIFORNIA STATE ARCHITECTURE BOARD. ARCHITECTURAL DRAWING STANDARDS. 2011.
- 12. CALIFORNIA STATE ARCHITECTURE BOARD. ARCHITECTURAL DRAWING STANDARDS. 2011.
- 13. CALIFORNIA STATE ARCHITECTURE BOARD. ARCHITECTURAL DRAWING STANDARDS. 2011.
- 14. CALIFORNIA STATE ARCHITECTURE BOARD. ARCHITECTURAL DRAWING STANDARDS. 2011.
- 15. CALIFORNIA STATE ARCHITECTURE BOARD. ARCHITECTURAL DRAWING STANDARDS. 2011.
- 16. CALIFORNIA STATE ARCHITECTURE BOARD. ARCHITECTURAL DRAWING STANDARDS. 2011.
- 17. CALIFORNIA STATE ARCHITECTURE BOARD. ARCHITECTURAL DRAWING STANDARDS. 2011.
- 18. CALIFORNIA STATE ARCHITECTURE BOARD. ARCHITECTURAL DRAWING STANDARDS. 2011.
- 19. CALIFORNIA STATE ARCHITECTURE BOARD. ARCHITECTURAL DRAWING STANDARDS. 2011.
- 20. CALIFORNIA STATE ARCHITECTURE BOARD. ARCHITECTURAL DRAWING STANDARDS. 2011.


EXTENSION COLUMN SCHEDULE

1	EXTENSION COLUMN
2	EXTENSION COLUMN
3	EXTENSION COLUMN
4	EXTENSION COLUMN
5	EXTENSION COLUMN
6	EXTENSION COLUMN
7	EXTENSION COLUMN
8	EXTENSION COLUMN
9	EXTENSION COLUMN
10	EXTENSION COLUMN
11	EXTENSION COLUMN
12	EXTENSION COLUMN
13	EXTENSION COLUMN
14	EXTENSION COLUMN
15	EXTENSION COLUMN
16	EXTENSION COLUMN
17	EXTENSION COLUMN
18	EXTENSION COLUMN
19	EXTENSION COLUMN
20	EXTENSION COLUMN


1. PERRIS TRUCK YARD, 3RD PLANNING SUBMITTAL, 2011.
2. CALIFORNIA STATE ARCHITECTURE BOARD, ARCHITECTURAL DRAWING STANDARDS, 2011.
3. AMERICAN INSTITUTE OF ARCHITECTS, ARCHITECTURAL DRAWING VocabularY, 2003.
4. CALIFORNIA STATE ARCHITECTURE BOARD, ARCHITECTURAL DRAWING STANDARDS, 2011.
5. CALIFORNIA STATE ARCHITECTURE BOARD, ARCHITECTURAL DRAWING STANDARDS, 2011.
6. CALIFORNIA STATE ARCHITECTURE BOARD, ARCHITECTURAL DRAWING STANDARDS, 2011.
7. CALIFORNIA STATE ARCHITECTURE BOARD, ARCHITECTURAL DRAWING STANDARDS, 2011.
8. CALIFORNIA STATE ARCHITECTURE BOARD, ARCHITECTURAL DRAWING STANDARDS, 2011.
9. CALIFORNIA STATE ARCHITECTURE BOARD, ARCHITECTURAL DRAWING STANDARDS, 2011.
10. CALIFORNIA STATE ARCHITECTURE BOARD, ARCHITECTURAL DRAWING STANDARDS, 2011.
11. CALIFORNIA STATE ARCHITECTURE BOARD, ARCHITECTURAL DRAWING STANDARDS, 2011.
12. CALIFORNIA STATE ARCHITECTURE BOARD, ARCHITECTURAL DRAWING STANDARDS, 2011.
13. CALIFORNIA STATE ARCHITECTURE BOARD, ARCHITECTURAL DRAWING STANDARDS, 2011.
14. CALIFORNIA STATE ARCHITECTURE BOARD, ARCHITECTURAL DRAWING STANDARDS, 2011.
15. CALIFORNIA STATE ARCHITECTURE BOARD, ARCHITECTURAL DRAWING STANDARDS, 2011.
16. CALIFORNIA STATE ARCHITECTURE BOARD, ARCHITECTURAL DRAWING STANDARDS, 2011.
17. CALIFORNIA STATE ARCHITECTURE BOARD, ARCHITECTURAL DRAWING STANDARDS, 2011.
18. CALIFORNIA STATE ARCHITECTURE BOARD, ARCHITECTURAL DRAWING STANDARDS, 2011.
19. CALIFORNIA STATE ARCHITECTURE BOARD, ARCHITECTURAL DRAWING STANDARDS, 2011.
20. CALIFORNIA STATE ARCHITECTURE BOARD, ARCHITECTURAL DRAWING STANDARDS, 2011.



① EAST TRUCK YARD - SITE WALL ELEVATION



② EAST TRUCK YARD - SITE WALL ELEVATION



④ EAST TRUCK YARD - NORTHEAST GATE ELEVATION

REFERENCE


- 1. SEE SHEET 1.1 FOR GENERAL NOTES AND SPECIFICATIONS.
- 2. SEE SHEET 1.2 FOR GENERAL NOTES AND SPECIFICATIONS.
- 3. SEE SHEET 1.3 FOR GENERAL NOTES AND SPECIFICATIONS.
- 4. SEE SHEET 1.4 FOR GENERAL NOTES AND SPECIFICATIONS.
- 5. SEE SHEET 1.5 FOR GENERAL NOTES AND SPECIFICATIONS.
- 6. SEE SHEET 1.6 FOR GENERAL NOTES AND SPECIFICATIONS.
- 7. SEE SHEET 1.7 FOR GENERAL NOTES AND SPECIFICATIONS.
- 8. SEE SHEET 1.8 FOR GENERAL NOTES AND SPECIFICATIONS.
- 9. SEE SHEET 1.9 FOR GENERAL NOTES AND SPECIFICATIONS.
- 10. SEE SHEET 1.10 FOR GENERAL NOTES AND SPECIFICATIONS.

- EXTENSION COLOR SCHEDULE**
- ① EXTENSION COLOR
 - ② EXTENSION COLOR
 - ③ EXTENSION COLOR
 - ④ EXTENSION COLOR
 - ⑤ EXTENSION COLOR
 - ⑥ EXTENSION COLOR
 - ⑦ EXTENSION COLOR
 - ⑧ EXTENSION COLOR
 - ⑨ EXTENSION COLOR
 - ⑩ EXTENSION COLOR


NOTES

1. ALL DIMENSIONS ARE IN FEET AND INCHES.
2. ALL DIMENSIONS ARE TO FACE UNLESS OTHERWISE NOTED.
3. ALL DIMENSIONS ARE TO CENTERLINE UNLESS OTHERWISE NOTED.
4. ALL DIMENSIONS ARE TO THE CENTERLINE OF THE WALL UNLESS OTHERWISE NOTED.
5. ALL DIMENSIONS ARE TO THE CENTERLINE OF THE DOOR UNLESS OTHERWISE NOTED.
6. ALL DIMENSIONS ARE TO THE CENTERLINE OF THE WINDOW UNLESS OTHERWISE NOTED.
7. ALL DIMENSIONS ARE TO THE CENTERLINE OF THE PANEL UNLESS OTHERWISE NOTED.
8. ALL DIMENSIONS ARE TO THE CENTERLINE OF THE PANEL UNLESS OTHERWISE NOTED.
9. ALL DIMENSIONS ARE TO THE CENTERLINE OF THE PANEL UNLESS OTHERWISE NOTED.
10. ALL DIMENSIONS ARE TO THE CENTERLINE OF THE PANEL UNLESS OTHERWISE NOTED.







1 NORTH ELEVATION
1" = 48'-0"




3 DOCK SIDE RETURN ELEVATION
1" = 48'-0"




2 SOUTH ELEVATION
1" = 48'-0"



6 DOCK SIDE RETURN ELEVATION
1" = 48'-0"



3 WEST ELEVATION
1" = 48'-0"





4 EAST ELEVATION
1" = 48'-0"


KEY	DESCRIPTION
[Symbol]	ENTRANCES
[Symbol]	1. EXTERIOR WALLS
[Symbol]	2. ROOF
[Symbol]	3. FLOOR
[Symbol]	4. WALL
[Symbol]	5. WINDOW
[Symbol]	6. DOOR
[Symbol]	7. GLASS
[Symbol]	8. METAL PANEL
[Symbol]	9. BRICK
[Symbol]	10. CONCRETE
[Symbol]	11. STONE
[Symbol]	12. TERRAZZO
[Symbol]	13. CERAMIC TILE
[Symbol]	14. POLISHED CONCRETE
[Symbol]	15. PAINTED CONCRETE
[Symbol]	16. PAINTED BRICK
[Symbol]	17. PAINTED STONE
[Symbol]	18. PAINTED METAL
[Symbol]	19. PAINTED GLASS
[Symbol]	20. PAINTED DOOR
[Symbol]	21. PAINTED WINDOW
[Symbol]	22. PAINTED GLASS BLOCK
[Symbol]	23. PAINTED METAL PANEL
[Symbol]	24. PAINTED BRICK
[Symbol]	25. PAINTED STONE
[Symbol]	26. PAINTED TERRAZZO
[Symbol]	27. PAINTED CERAMIC TILE
[Symbol]	28. PAINTED POLISHED CONCRETE
[Symbol]	29. PAINTED PAINTED CONCRETE





ENLARGED VIEW @ CORNER


- 


PAINTED CONCRETE PANEL
A. SW 7005
PURE WHITE
- 

PAINTED CONCRETE PANEL
B. SW 6252
ICE CUBE
- 

PAINTED CONCRETE PANEL
C. SW 6254
LAZY GRAY
- 

PAINTED CONCRETE PANEL
D. SW 7069
IRON ORE
- 

E. CONCRETE
FORMLINER
SW 7650
ELLIE GRAY
- 

F. BLACK ANODIZED
DECORATIVE METAL
- 


G. STOREFRONT
MEDIUM
PERFORMANCE
BRONZE REFLECTIVE
GLAZING & BLACK
ANODIZED MULLIONS

PATTERSON & NANCE
FERRIS, CA

PROJECT
3RD PLANNING SUBMITTAL



HERDMAN
ARCHITECTURE + DESIGN
A17-0011
04.24.2013
MATERIAL
BOARD



HERDMAN
ARCHITECTURE • DESIGN

**PROLOGIS
PATTERSON & NANCE - PERRIS, CA**

04.21.2023
H-A+D JOB NO: A21-2001



NOTE: ALL EXTERIOR LIGHTS TO BE 5000K COLOR TEMP

FIGURE LEGEND


SYMBOL	DESCRIPTION	FIGURE NUMBER	HEIGHT FROM FINISH GRADE
[Symbol]	1. WALL MOUNTED RECESSED DOWN LIGHT 2. 1/2" x 2" x 2" SQUARE RECESSED DOWN LIGHT 3. 1/4" x 1" x 1" SQUARE RECESSED DOWN LIGHT 4. 1/8" x 1/2" x 1/2" SQUARE RECESSED DOWN LIGHT 5. 1/4" x 1" x 1" SQUARE RECESSED DOWN LIGHT 6. 1/8" x 1/2" x 1/2" SQUARE RECESSED DOWN LIGHT	E100001 - E100006	100, 125, 150, 175, 200, 225, 250, 275, 300, 325, 350, 375, 400, 425, 450, 475, 500, 525, 550, 575, 600, 625, 650, 675, 700, 725, 750, 775, 800, 825, 850, 875, 900, 925, 950, 975, 1000
[Symbol]	1. DOWN LIGHT 2. 1/2" x 2" x 2" SQUARE DOWN LIGHT 3. 1/4" x 1" x 1" SQUARE DOWN LIGHT 4. 1/8" x 1/2" x 1/2" SQUARE DOWN LIGHT 5. 1/4" x 1" x 1" SQUARE DOWN LIGHT 6. 1/8" x 1/2" x 1/2" SQUARE DOWN LIGHT	E100007 - E100012	100, 125, 150, 175, 200, 225, 250, 275, 300, 325, 350, 375, 400, 425, 450, 475, 500, 525, 550, 575, 600, 625, 650, 675, 700, 725, 750, 775, 800, 825, 850, 875, 900, 925, 950, 975, 1000
[Symbol]	1. WALL MOUNTED DOWN LIGHT 2. 1/2" x 2" x 2" SQUARE WALL MOUNTED DOWN LIGHT 3. 1/4" x 1" x 1" SQUARE WALL MOUNTED DOWN LIGHT 4. 1/8" x 1/2" x 1/2" SQUARE WALL MOUNTED DOWN LIGHT 5. 1/4" x 1" x 1" SQUARE WALL MOUNTED DOWN LIGHT 6. 1/8" x 1/2" x 1/2" SQUARE WALL MOUNTED DOWN LIGHT	E100013 - E100018	100, 125, 150, 175, 200, 225, 250, 275, 300, 325, 350, 375, 400, 425, 450, 475, 500, 525, 550, 575, 600, 625, 650, 675, 700, 725, 750, 775, 800, 825, 850, 875, 900, 925, 950, 975, 1000
[Symbol]	1. TRACK LIGHT 2. 1/2" x 2" x 2" SQUARE TRACK LIGHT 3. 1/4" x 1" x 1" SQUARE TRACK LIGHT 4. 1/8" x 1/2" x 1/2" SQUARE TRACK LIGHT 5. 1/4" x 1" x 1" SQUARE TRACK LIGHT 6. 1/8" x 1/2" x 1/2" SQUARE TRACK LIGHT	E100019 - E100024	100, 125, 150, 175, 200, 225, 250, 275, 300, 325, 350, 375, 400, 425, 450, 475, 500, 525, 550, 575, 600, 625, 650, 675, 700, 725, 750, 775, 800, 825, 850, 875, 900, 925, 950, 975, 1000
[Symbol]	1. RECESSED DOWN LIGHT 2. 1/2" x 2" x 2" SQUARE RECESSED DOWN LIGHT 3. 1/4" x 1" x 1" SQUARE RECESSED DOWN LIGHT 4. 1/8" x 1/2" x 1/2" SQUARE RECESSED DOWN LIGHT 5. 1/4" x 1" x 1" SQUARE RECESSED DOWN LIGHT 6. 1/8" x 1/2" x 1/2" SQUARE RECESSED DOWN LIGHT	E100025 - E100030	100, 125, 150, 175, 200, 225, 250, 275, 300, 325, 350, 375, 400, 425, 450, 475, 500, 525, 550, 575, 600, 625, 650, 675, 700, 725, 750, 775, 800, 825, 850, 875, 900, 925, 950, 975, 1000
[Symbol]	1. DOWN LIGHT 2. 1/2" x 2" x 2" SQUARE DOWN LIGHT 3. 1/4" x 1" x 1" SQUARE DOWN LIGHT 4. 1/8" x 1/2" x 1/2" SQUARE DOWN LIGHT 5. 1/4" x 1" x 1" SQUARE DOWN LIGHT 6. 1/8" x 1/2" x 1/2" SQUARE DOWN LIGHT	E100031 - E100036	100, 125, 150, 175, 200, 225, 250, 275, 300, 325, 350, 375, 400, 425, 450, 475, 500, 525, 550, 575, 600, 625, 650, 675, 700, 725, 750, 775, 800, 825, 850, 875, 900, 925, 950, 975, 1000
[Symbol]	1. WALL MOUNTED DOWN LIGHT 2. 1/2" x 2" x 2" SQUARE WALL MOUNTED DOWN LIGHT 3. 1/4" x 1" x 1" SQUARE WALL MOUNTED DOWN LIGHT 4. 1/8" x 1/2" x 1/2" SQUARE WALL MOUNTED DOWN LIGHT 5. 1/4" x 1" x 1" SQUARE WALL MOUNTED DOWN LIGHT 6. 1/8" x 1/2" x 1/2" SQUARE WALL MOUNTED DOWN LIGHT	E100037 - E100042	100, 125, 150, 175, 200, 225, 250, 275, 300, 325, 350, 375, 400, 425, 450, 475, 500, 525, 550, 575, 600, 625, 650, 675, 700, 725, 750, 775, 800, 825, 850, 875, 900, 925, 950, 975, 1000
[Symbol]	1. TRACK LIGHT 2. 1/2" x 2" x 2" SQUARE TRACK LIGHT 3. 1/4" x 1" x 1" SQUARE TRACK LIGHT 4. 1/8" x 1/2" x 1/2" SQUARE TRACK LIGHT 5. 1/4" x 1" x 1" SQUARE TRACK LIGHT 6. 1/8" x 1/2" x 1/2" SQUARE TRACK LIGHT	E100043 - E100048	100, 125, 150, 175, 200, 225, 250, 275, 300, 325, 350, 375, 400, 425, 450, 475, 500, 525, 550, 575, 600, 625, 650, 675, 700, 725, 750, 775, 800, 825, 850, 875, 900, 925, 950, 975, 1000
[Symbol]	1. DOWN LIGHT 2. 1/2" x 2" x 2" SQUARE DOWN LIGHT 3. 1/4" x 1" x 1" SQUARE DOWN LIGHT 4. 1/8" x 1/2" x 1/2" SQUARE DOWN LIGHT 5. 1/4" x 1" x 1" SQUARE DOWN LIGHT 6. 1/8" x 1/2" x 1/2" SQUARE DOWN LIGHT	E100049 - E100054	100, 125, 150, 175, 200, 225, 250, 275, 300, 325, 350, 375, 400, 425, 450, 475, 500, 525, 550, 575, 600, 625, 650, 675, 700, 725, 750, 775, 800, 825, 850, 875, 900, 925, 950, 975, 1000
[Symbol]	1. WALL MOUNTED DOWN LIGHT 2. 1/2" x 2" x 2" SQUARE WALL MOUNTED DOWN LIGHT 3. 1/4" x 1" x 1" SQUARE WALL MOUNTED DOWN LIGHT 4. 1/8" x 1/2" x 1/2" SQUARE WALL MOUNTED DOWN LIGHT 5. 1/4" x 1" x 1" SQUARE WALL MOUNTED DOWN LIGHT 6. 1/8" x 1/2" x 1/2" SQUARE WALL MOUNTED DOWN LIGHT	E100055 - E100060	100, 125, 150, 175, 200, 225, 250, 275, 300, 325, 350, 375, 400, 425, 450, 475, 500, 525, 550, 575, 600, 625, 650, 675, 700, 725, 750, 775, 800, 825, 850, 875, 900, 925, 950, 975, 1000
[Symbol]	1. TRACK LIGHT 2. 1/2" x 2" x 2" SQUARE TRACK LIGHT 3. 1/4" x 1" x 1" SQUARE TRACK LIGHT 4. 1/8" x 1/2" x 1/2" SQUARE TRACK LIGHT 5. 1/4" x 1" x 1" SQUARE TRACK LIGHT 6. 1/8" x 1/2" x 1/2" SQUARE TRACK LIGHT	E100061 - E100066	100, 125, 150, 175, 200, 225, 250, 275, 300, 325, 350, 375, 400, 425, 450, 475, 500, 525, 550, 575, 600, 625, 650, 675, 700, 725, 750, 775, 800, 825, 850, 875, 900, 925, 950, 975, 1000

* * SEE ARCHITECTURAL PLANS FOR ACTUAL POLE BASE HEIGHTS

THE SITE LIGHTING STATISTICS

CAL GREEN BUG TABLE

1. LIGHT FIXTURE	2. LIGHTING TYPE	3. LIGHTING TYPE	4. LIGHTING TYPE	5. LIGHTING TYPE	6. LIGHTING TYPE	7. LIGHTING TYPE	8. LIGHTING TYPE	9. LIGHTING TYPE	10. LIGHTING TYPE	11. LIGHTING TYPE	12. LIGHTING TYPE	13. LIGHTING TYPE	14. LIGHTING TYPE	15. LIGHTING TYPE	16. LIGHTING TYPE	17. LIGHTING TYPE	18. LIGHTING TYPE	19. LIGHTING TYPE	20. LIGHTING TYPE		



SITE LIGHTING PLAN
SCALE: 1/8"=1'-0"

SITE LIGHTING STATISTICS

1. TOTAL LIGHTING FIXTURES: [Value]

2. TOTAL LIGHTING FIXTURES: [Value]

3. TOTAL LIGHTING FIXTURES: [Value]

4. TOTAL LIGHTING FIXTURES: [Value]

5. TOTAL LIGHTING FIXTURES: [Value]

CONTRACTORS
J.B. Mc. BIRCH

Gay
Electric
Inc.

800 W. SARDINA ST.
ORANGE, CA 92667
(714) 952-1900

PROJECT: PROLOGIS PATTERSON & NANNICE

TITLE: SITE LIGHTING PLAN

DATE: [Value]

SCALE: [Value]

DATE: 08-10-2017


BY: [Value]

CHECKED BY: [Value]

SCALE: [Value]

22620

ESL1



BUILDING


PATTERSON AVENUE

NEVADA AVENUE

NANCE STREET

1. ALL PLANTING IS TO BE INSTALLED BY THE CONTRACTOR AND SHALL BE SUBJECT TO THE SUPERVISOR'S APPROVAL.
2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES AND TREES.
3. THE CONTRACTOR SHALL MAINTAIN ACCESS TO ALL ADJACENT PROPERTIES AT ALL TIMES.
4. THE CONTRACTOR SHALL MAINTAIN ALL STREETS AND SIDEWALKS IN GOOD REPAIR THROUGHOUT THE CONSTRUCTION PERIOD.
5. THE CONTRACTOR SHALL MAINTAIN ALL NEIGHBORHOODS AND AREAS AFFECTED BY THE PROJECT.
6. THE CONTRACTOR SHALL MAINTAIN ALL NEIGHBORHOODS AND AREAS AFFECTED BY THE PROJECT.
7. THE CONTRACTOR SHALL MAINTAIN ALL NEIGHBORHOODS AND AREAS AFFECTED BY THE PROJECT.
8. THE CONTRACTOR SHALL MAINTAIN ALL NEIGHBORHOODS AND AREAS AFFECTED BY THE PROJECT.
9. THE CONTRACTOR SHALL MAINTAIN ALL NEIGHBORHOODS AND AREAS AFFECTED BY THE PROJECT.
10. THE CONTRACTOR SHALL MAINTAIN ALL NEIGHBORHOODS AND AREAS AFFECTED BY THE PROJECT.

PLANTING LEGEND	SYMBOL	PLANT SPECIES	QUANTITY	NOTES
(Symbol)	1
(Symbol)	2
(Symbol)	3
(Symbol)	4
(Symbol)	5
(Symbol)	6
(Symbol)	7
(Symbol)	8
(Symbol)	9
(Symbol)	10



PROLOGIS PATTERSON & NANCE

21-2511
 11/13/2011
 7/4/10, 3/08, 3/08

Perris, California



HUNTER LANDSCAPE
 711 EEE 54th STREET PLACENTIA, CA 92679
 714.988.3488 FAX 714.988.3488




PLANTING LEGEND

SYMBOL	PLANT NAME	QUANTITY	PLANT SPECIES
[Symbol]	Plant Name	100	Plant Species
[Symbol]	Plant Name	200	Plant Species
[Symbol]	Plant Name	300	Plant Species
[Symbol]	Plant Name	400	Plant Species
[Symbol]	Plant Name	500	Plant Species
[Symbol]	Plant Name	600	Plant Species
[Symbol]	Plant Name	700	Plant Species
[Symbol]	Plant Name	800	Plant Species
[Symbol]	Plant Name	900	Plant Species
[Symbol]	Plant Name	1000	Plant Species

PLANTING AREA	PLANT SPECIES	PLANT SIZE	PLANT QUANTITY
Area 1	Plant Species	Plant Size	Plant Quantity
Area 2	Plant Species	Plant Size	Plant Quantity
Area 3	Plant Species	Plant Size	Plant Quantity
Area 4	Plant Species	Plant Size	Plant Quantity
Area 5	Plant Species	Plant Size	Plant Quantity
Area 6	Plant Species	Plant Size	Plant Quantity
Area 7	Plant Species	Plant Size	Plant Quantity
Area 8	Plant Species	Plant Size	Plant Quantity
Area 9	Plant Species	Plant Size	Plant Quantity
Area 10	Plant Species	Plant Size	Plant Quantity

1. All quantities are for the entire project.
2. All quantities are for the entire project.
3. All quantities are for the entire project.
4. All quantities are for the entire project.
5. All quantities are for the entire project.
6. All quantities are for the entire project.
7. All quantities are for the entire project.
8. All quantities are for the entire project.
9. All quantities are for the entire project.
10. All quantities are for the entire project.



PROLOGIS PATTERSON & NANCE

21-031
 01.01 2/28/12

Perris, California

HUNTER LANDSCAPE
 711 7th Ave Street | Perris, CA 92570
 714.989.2000 | Fax: 714.989.3488

EXHIBIT H

Environmental Impact Report (SCH:2022010274)

(due to the size of the files, the documents are located at the following webpage link):

https://www.cityofperris.org/departments/development-services/planning/environmental-documents-for-public-review/-folder-333#docan1206_1313_479